

**UNDERGROUND INJECTION CONTROL
AREA PERMIT REAPPLICATION
FOR
GROUND RESOURCES, LLC**

**UIC PERMIT No. 2R08700008AP
TARIFF FIELD**

**Volume 1 of 4
(Sections 1 to 16)**

CHECKLIST FOR FILING A UIC PERMIT APPLICATION

Please utilize this checklist to ensure you have prepared, completed, and enclosed all required documentation and payment to ensure a timely review of your submittal.

Operator	Ground Resources, LLC		
Existing UIC Permit ID Number	2R08700008AP	UIC Well API Number	SEE ATTACHED

Office of Oil and Gas Office Use Only	
Permit Reviewer	A. Lockwood
Date Received	10/31/17
Administratively Complete Date	9/15/20
Approved Date	10/01/20
Permit Issued	

Please check the fees and payment included.

Fees		Payment Type	
UIC Permit Fee: \$500	<input checked="" type="checkbox"/>	Check -14734	<input checked="" type="checkbox"/>
Groundwater Protection Plan (GPP) Fee: \$50.00	<input checked="" type="checkbox"/>	Electronic	<input type="checkbox"/>
		Other	<input type="checkbox"/>

Please check the items completed and enclosed.

- ☒ Checklist
- ☒ UIC-1
 - ☒ Section 1 – Facility Information
 - ☒ Section 2 – Operator Information
 - ☒ Section 3 – Application Information
 - ☒ Section 4 – Applicant/Activity Request and Type
 - ☒ Section 5 – Brief description of the Nature of the Business
 - ☒ CERTIFICATION
- ☒ Section 6 – Construction
 - ☒ Appendix A Injection Well Form
 - ☒ Appendix B Storage Tank Inventory
- ☒ Section 7 – Area of Review
 - ☒ Appendix C Wells Within the Area of Review


- ☒ Appendix D Public Service District Affidavit
- ☒ Appendix E Water Sources
- ☒ Appendix F Area Permit Wells
- ☒ Section 8 – Geological Data on Injection and Confining Zones
- ☒ Section 9 – Operating Requirements / Data
 - ☒ Appendix G Wells Serviced by Injection Well
- ☒ Section 10 – Monitoring
- ☒ Section 11 – Groundwater Protection Plan (GPP)
 - ☒ Appendix H Groundwater Protection Plan (GPP)
- ☒ Section 12 – Plugging and Abandonment
- ☐ Section 13 – Additional Bonding -NA
- ☒ Section 14 – Financial Responsibility
 - ☒ Appendix I Financial Responsibility
- ☐ Section 15 – Site Security Plan -NA
 - ☐ Appendix J Site Security for Commercial Wells -NA
- ☒ Section 16 – Additional Information
 - ☒ Appendix K Other Permit Approvals

***NOTE: For all 2D wells an additional bond in the amount of \$5,000 is required.**

Reviewed by (Print Name): Blake E. Jones

Reviewed by (Sign): Blake E. Jones

Date Reviewed: 9.28.2020

	WEST VIRGINIA DEPARTMENT OF ENVIRONMENTAL PROTECTION OFFICE OF OIL AND GAS 601 57 th Street, SE Charleston, WV 25304 (304) 826-0450 www.dep.wv.gov/oil-and-gas	UNDERGROUND INJECTION CONTROL (UIC) PERMIT APPLICATION
	UIC PERMIT ID # <u>2R08700008AP</u> API # <u>SEE ATTACHED</u> WELL # <u>TARIFF FIELD</u>	

Section 1. Facility Information

Facility Name: TARIFF FIELD		
Address: 1422 TARIFF ROAD		
City: Left Hand	State: WV	Zip: 25251
County: Roane	District: Smithfield & Geary	
Location description: From the city of Charleston, WV, travel North on I-77 for approx. 1.6 miles. Keep right to continue on I-79 North, follow signs for Clarkburg, and travel for approx. 25.1 miles. Take exit 25 toward Amma and travel approx. 0.4 miles. Turn right onto Co. Route 29/Amma Road and travel approx. 0.7 miles. Take the first left onto Amma Road/Co. Route 58/2 and continue to follow Amma Rd. for approx. 3.6 miles. Turn right onto WV-36 South and travel approx. 0.6 miles. Take a slight left onto Co. Route 60/Tariff Road and travel approx. 1.6 miles. Take a slight right and travel approx. 0.3 miles. The facility will be on the left.		
Location of well(s) or approximate center of field/project in UTM NAD 83 (meters): Northing: 4279357.4		Easting: 481520.87 Lat. 38.6626 Long. -81.2124
Environmental Contact Information: Name: Jon Hall Adam Linkinogger Title: Supervisor Phone: 304-587-4477 Email: jon.hall@groundresourcesllc.com adam.linkinogger		

Section 2. Operator Information

Operator Name: GROUND RESOURCES, LLC	
Operator ID: 494520132	
Address: 513 Charleston Road	
City: Spencer	State: WV Zip: 25276
County: Roane	
Contact Name: Erica Nichols	Contact Title: Office Manager
Contact Phone: 304-927-2996	Contact Email: erica@hettar1.com

Section 3. Applicant Information

Ownership Status: ☒ PRIVATE ☐ PUBLIC ☐ FEDERAL ☐ STATE
☐ OTHER (explain):

SIC code: ☒ 1311 (2D, 2H, 2R) ☐ 1479 (3S) ☐ OTHER (explain):

Section 4. Applicant / Activity Request and Type:

- A. Apply for a new UIC Permit: ☐ 2D ☐ 2H ☐ 2R ☐ 3S
B. Reissue existing UIC Permit: ☐ 2D ☐ 2H ☒ 2R ☐ 3S
C. Modify existing UIC Permit: ☐ 2D ☐ 2H ☐ 2R ☐ 3S
(Submit only documentation pertaining to the modification request)
2D COMMERCIAL FACILITY: ☐ YES ☒ NO

Section 5. Briefly describe the nature of business and the activities to be conducted:

Oil and/or Gas production. Subsurface injection of produced and/or fresh water into the Big Injun formation for the secondary recovery of oil.

CERTIFICATION

All permit applications must be signed by a responsible corporate officer for a corporation, by a general partner for a partnership, by the proprietor of a sole proprietorship, or by a principal executive or ranking elected official for a public agency, or a ¹duly authorized representative in accordance with 47CSR13-13.11.b.

A. Name and title of person applying for permit:

Print Name: David W Heeter
Print Title: Owner

B. Signature and Date.

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

Signature: David W Heeter
Date: 9/25/2020

¹ A person is a duly authorized representative if:

The authorization is made in writing by a person described in subdivision 47CSR13-13.11.a.

The authorization specifies either an individual or a position having responsibility for the overall operation of the regulated facility or activity, such as the position of the plant manager, operator of a well or a well field, superintendent, or position of equivalent responsibility.

The written authorization is submitted to the Director.

Section 6

Construction

Ground Resources, LLC
Tariff Field
Permit No. 2R08700008AP

Appendix B – Storage Tank Inventory
Injection Facility Site Map
Secondary Containment Calculations

TARIFF UIC
PERMIT
2R8700008AP

TARIFF UNIT
TANK BATTERY

PUMP HOUSE

PIPELINE FROM PUMPHOUSE TO 3604

38.6492° N, 81.32084°W

3604

PROPOSED PIPELINE FROM 3604 to 2080

38.6469°N, 81.2199°W

2080

TARIFF UNIT TANK BATTERY
PIPELINE OVERVIEW


NOT TO SCALE




TARIFF UNIT TANK
BATTERY
SITE DIAGRAM
2R8700008AP

NOT TO SCALE

FOR ALL SECONDARY CONTAINMENT
CALCULATIONS - SEE ATTACHMENT






Promoting a healthy environment.

Tariff Field
UIC Permit
2R870008AP

Oil Storage Tanks Plumbing Schematic (not to scale)

Ground Resources, LLC
7/6/2020



Ground Resources, LLC
 Tariff Field
 UIC 2R08700008AP

Secondary Containment Calculations

Oil Storage Area (6 - 210 bbl Tanks)

Earth Berm Containment

(Input Measurements In Blue Cells)

Tank	Tank Dimensions		Capacity		
	Height (Ft)	Dia (Ft)	Barrels	Gallons	Cu Ft
1	15.0125	10	210.0	8820.1	1179.1
2	15.0125	10	210.0	8820.1	1179.1
3	15.0125	10	210.0	8820.1	1179.1
4	15.0125	10	210.0	8820.1	1179.1
5	15.0125	10	210.0	8820.1	1179.1
6	15.0125	10	210.0	8820.1	1179.1
7			0.0	0.0	0.0
8			0.0	0.0	0.0
9			0.0	0.0	0.0
10			0.0	0.0	0.0
Total			1,260.0	52,920.7	7,074.5
Input Largest Tank as Tank No.1 Above					

Tank	Tank Base Exclusions		
	Dia (Ft)	Depth (Ft)	Vol (CuFt)
1	0	3.00	0.0
2	10	3.00	235.6
3	10	3.00	235.6
4	10	3.00	235.6
5	10	3.00	235.6
6	10	3.00	235.6
7	0	3.00	0.0
8	0	3.00	0.0
9	0	3.00	0.0
10	0	3.00	0.0
Total Tank Base Exclusions			1178.1
Enter "0" diameter for the largest volume tank to exclude it from the tank base exclusion calculations.			

Containment Dimensions	
Top Interior Perimeter	
Length (Ft)	Width (Ft)
68.00	38.00
Bottom Interior Perimeter	
Length (Ft)	Width (Ft)
62.00	32.00
Depth (Ft)	
3.00	
Total Containment Volume (CuFt)	6832.2
All containment measurements must be interior dimensions.	


Tank Containment Volume (CuFt)	6832.2
Minus Tank Base Exclusions (CuFt)	1178.1
Net Containment Volume (CuFt)	5654.1
Largest Tank Volume (CuFt)	1179.1
Available Containment Volume (CuFt)	479.5%

Tariff Field
UIC Permit
2R8700008AP

Injectate (Produced Brine) Tank Plumbing Schematic

Ground Resources, LLC
7/6/2020

(not to scale)



Ground Resources, LLC
 Tariff Field
 UIC 2R08700008AP

Secondary Containment Calculations

Brine Storage Area (1 - 210 bbl Tank)

Earth Berm Containment


(Input Measurements In Blue Cells)

Tank	Tank Dimensions		Capacity		
	Height (Ft)	Dia (Ft)	Barrels	Gallons	Cu Ft
1	15.0125	10	210.0	8820.1	1179.1
2			0.0	0.0	0.0
3			0.0	0.0	0.0
4			0.0	0.0	0.0
5			0.0	0.0	0.0
6			0.0	0.0	0.0
7			0.0	0.0	0.0
8			0.0	0.0	0.0
9			0.0	0.0	0.0
10			0.0	0.0	0.0
Total			210.0	8,820.1	1,179.1
Input Largest Tank as Tank No.1 Above					

Tank	Tank Base Exclusions		
	Dia (Ft)	Depth (Ft)	Vol (CuFt)
1	0	3.00	0.0
2	0	3.00	0.0
3	0	3.00	0.0
4	0	3.00	0.0
5	0	3.00	0.0
6	0	3.00	0.0
7	0	3.00	0.0
8	0	3.00	0.0
9	0	3.00	0.0
10	0	3.00	0.0
Total Tank Base Exclusions			0.0
Enter "0" diameter for the largest volume tank to exclude it from the tank base exclusion calculations.			


Containment Dimensions	
Top Interior Perimeter	
Length (Ft)	Width (Ft)
68.00	44.00
Bottom Interior Perimeter	
Length (Ft)	Width (Ft)
62.00	38.00
Depth (Ft)	
3.00	
Total Containment Volume (CuFt)	8003.0
All containment measurements must be interior dimensions.	

Tank Containment Volume (CuFt)	8003.0
Minus Tank Base Exclusions (CuFt)	0.0
Net Containment Volume (CuFt)	8003.0
Largest Tank Volume (CuFt)	1179.1
Available Containment Volume (CuFt)	678.8%



From Production Wells
Multiple oil lines connect to
pump house

PUMP HOUSE



Ground Resources, LLC
Tariff Field
UIC 2R08700008AP

Secondary Containment Calculations

Oil Separator Storage Area (1 - 70 bbl Tank, 1 - 30 bbl Tank)

Earth Berm Containment

(Input Measurements in Blue Cells)

Tank	Tank Dimensions		Capacity		
	Height (Ft)	Dia (Ft)	Barrels	Gallons	Cu Ft
1	20	5	69.94	2937.6	392.7
2	13.5	4	30.2	1269.0	169.6
3			0.0	0.0	0.0
4			0.0	0.0	0.0
5			0.0	0.0	0.0
6			0.0	0.0	0.0
7			0.0	0.0	0.0
8			0.0	0.0	0.0
9			0.0	0.0	0.0
10			0.0	0.0	0.0
Total			100.2	4,206.6	562.3
Input Largest Tank as Tank No.1 Above					

Tank	Tank Base Exclusions		
	Dia (Ft)	Depth (Ft)	Vol (CuFt)
1	0	1.00	0.0
2	4	1.00	12.6
3	0	1.00	0.0
4	0	1.00	0.0
5	0	1.00	0.0
6	0	1.00	0.0
7	0	1.00	0.0
8	0	1.00	0.0
9	0	1.00	0.0
10	0	1.00	0.0
Total Tank Base Exclusions			12.6
Enter "0" diameter for the largest volume tank to exclude it from the tank base exclusion calculations.			

Containment Dimensions	
Top Interior Perimeter	
Length (Ft)	Width (Ft)
56.00	24.00
Bottom Interior Perimeter	
Length (Ft)	Width (Ft)
54.00	22.00
Depth (Ft)	
1.00	
Total Containment Volume (CuFt)	1265.2
All containment measurements must be interior dimensions.	

Tank Containment Volume (CuFt)	1265.2
Minus Tank Base Exclusions (CuFt)	12.6
Net Containment Volume (CuFt)	1252.6
Largest Tank Volume (CuFt)	392.7
Available Containment Volume (CuFt)	319.0%

Section 7

Area of Review

Injector Well Construction Data

All injector well construction data including Appendix A, Wellbore Diagrams, Completion Logs, and E-logs are contained in a separate volume of this application.

AOR Well Data

All AOR well data is contained in a separate volume of this application.

Appendix C
All Wells in 1/4 Mile AOR

Ground Resources, LLC
2R08700008AP
Tariff Field

	API No.	Well Name	Well Type	Well Status	Easting	Northing
1	4708700444	Looney 27	2R Oil Production	Active Well	481379.9	4278542.9
2	4708700701	Looney 28	Fluid Injection	Shut-In	481656.0	4278648.0
3	4708700702	Looney 29	2R Oil Production	Active Well	481534.0	4278367.0
4	4708702079	Tallman 53	2R Oil Production	Abandoned Well	482841.0	4278791.0
5	4708702080	Tallman 54	Fluid Injection	Shut-In	481550.6	4277629.1
6	4708702405	Tallman 55	Fluid Injection	Shut-In	481849.0	4277612.0
7	4708702406	Tallman 56	Fluid Injection	Shut-In	481763.0	4277369.6
8	4708702407	Tallman 57	Fluid Injection	Shut-In	481558.3	4277327.8
9	4708702408	Tallman 58	Fluid Injection	Shut-In	481369.9	4277506.4
10	4708702409	Tallman 59	Fluid Injection	Shut-In	481337.3	4277597.0
11	4708702554	Hopkins 2	Fluid Injection	Plugged	481402.1	4277209.0
12	4708702633	Looney 1	2R Oil Production	Abandoned Well	481752.0	4279082.0
13	4708702634	Looney 3	2R Oil Production	Active Well	481370.2	4277860.8
14	4708702635	Looney 4	2R Oil Production	Plugged	481082.6	4278821.5
15	4708702636	Looney 5	2R Oil Production	Plugged	481678.0	4278187.0
16	4708702637	Looney 6	2R Oil Production	Abandoned Well	481822.6	427856.2
17	4708702638	Looney 7	Fluid Injection	Shut-In	481742.0	4278369.0
18	4708702639	Looney 8	2R Oil Production	Abandoned Well	481418.9	4278063.9
19	4708702641	Looney 10	2R Oil Production	Abandoned Well	481565.2	4278643.3
20	4708702643	Looney 12	2R Oil Production	Abandoned Well	481469.4	4279013.9
21	4708702644	Looney 15	2R Oil Production	Active Well	481325.1	4279271.9
22	4708702773	MJ Snodgrass 4	2R Oil Production	Abandoned Well	482455.5	4279494.9
23	4708702775	MJ Snodgrass 6	2R Oil Production	Abandoned Well	481642.0	4279591.0
24	4708702778	MJ Snodgrass 12	Fluid Injection	Shut-In	482826.1	4279392.6
25	4708702818	Tallman 1	2R Oil Production	Abandoned Well	482035.7	4278948.2
26	4708702820	Tallman 3	2R Oil Production	Active Well	481270.0	4277697.0
27	4708702821	Tallman 4	2R Oil Production	Abandoned Well	481922.7	4278787.4
28	4708702822	Tallman 5	2R Oil Production	Plugged	482077.6	4278187.0
29	4708702823	Tallman 6	2R Oil Production	Abandoned Well	481763.0	4277995.0
30	4708702824	Tallman 7	2R Oil Production	Abandoned Well	481978.0	4278573.0
31	4708702825	Tallman 8	2R Oil Production	Abandoned Well	481498.7	4277741.6
32	4708702826	Tallman 9	2R Oil Production	Abandoned Well	481970.0	4278368.6
33	4708702827	Tallman 10	2R Oil Production	Abandoned Well	482196.3	4278754.6
34	4708702828	Tallman 13	2R Oil Production	Abandoned Well	481921.3	4278175.5
35	4708702831	Tallman 19	2R Oil Production	Abandoned Well	481643.1	4277531.9
36	4708702832	Tallman 20	2R Oil Production	Active Well	481369.3	4277516.4
37	4708702833	Tallman 21	2R Oil Production	Active Well	481176.1	4277516.9
38	4708702835	Tallman 23	2R Oil Production	Abandoned Well	481969.1	4277966.0
39	4708702836	Tallman 25	2R Oil Production	Plugged	481835.0	4277485.1

40	4708702837	Tallman 26	2R Oil Production	Active Well	481320.6	4277323.3
41	4708702838	Tallman 31	Oil Production	Active Well	481787.1	4277128.9
42	4708702839	Tallman 32	Oil Production	Plugged	481851.8	4277241.5
43	4708702840	Tallman 33	Gas Production	Abandoned Well	480933.8	4277179.2
44	4708702844	Tallman 40	Fluid Injection	Shut-In	482567.9	4279365.8
45	4708702941	Tallman 60	Fluid Injection	Plugged	481640.1	4277855.2
46	4708703071	Looney 24	2R Oil Production	Active Well	481053.3	4278804.6
47	4708703083	Looney 14	2R Oil Production	Active Well	481179.0	4278512.0
48	4708703088	Looney 17	2R Oil Production	Plugged	481630.0	4279318.0
49	4708703095	Looney 16	2R Oil Production	Active Well	481061.3	4278267.1
50	4708703096	Looney 18	Fluid Injection	Shut-In	481486.8	4279529.4
51	4708703097	Looney 25	2R Oil Production	Active Well	481154.8	4279200.0
52	4708703127	Looney 23	2R Oil Production	Active Well	481231.0	4278994.9
53	4708703130	Tallman 17	2R Oil Production	Abandoned Well	482299.5	4279032.4
54	4708703134	Hopkins 3	2R Oil Production	Active Well	481134.7	4277126.4
55	4708703135	Tallman 12	2R Oil Production	Abandoned Well	481585.0	4277983.0
56	4708703136	MJ Snodgrass 3	2R Oil Production	Abandoned Well	482322.0	4279416.0
57	4708703138	Tallman 27	2R Oil Production	Plugged	481563.8	4277320.8
58	4708703167	Tallman 37	2R Oil Production	Abandoned Well	482245.9	4279102.0
59	4708703175	Tallman 24	2R Oil Production	Active Well	481977.0	4277721.0
60	4708703179	Looney 2	2R Oil Production	Plugged	481147.0	4277999.0
61	4708703181	Tallman 11	2R Oil Production	Active Well	482208.0	4278485.1
62	4708703604	Tallman 61	Fluid Injection	Shut-In	481870.8	4277883.6
63	4708703605	Tallman 62	Fluid Injection	Shut-In	481870.8	4277883.6
64	4708703608	Tallman 65	Fluid Injection	Shut-In	481227.5	4277766.9
65	4708703609	Tallman 66	Fluid Injection	Plugged	481344.0	4277830.0
66	4708703624	Tallman 30	2R Oil Production	Active Well	481128.0	4277379.0
67	4708703659	Looney 30	Fluid Injection	Plugged	481627.0	4278350.0
68	4708703660	Looney 31	Fluid Injection	Shut-In	481758.5	4278368.1
69	4708703661	Looney 32	Fluid Injection	Plugged	481471.0	4277996.0
70	4708703662	Looney 35	Fluid Injection	Plugged	481290.3	4278198.1
71	4708703663	Tallman 67	Fluid Injection	Plugged	481627.0	4278071.0
72	4708703664	Tallman 68	Fluid Injection	Plugged	481841.0	4278113.0
73	4708703674	Looney 33	Fluid Injection	Plugged	481329.2	4278001.7
74	4708703675	Looney 34	Fluid Injection	Plugged	481274.5	4278178.1
75	4708703766	Tallman 69	Fluid Injection	Plugged	482029.0	4278300.0
76	4708703767	Looney 36	Fluid Injection	Plugged	481677.5	4278466.8
77	4708703768	Looney 37	Fluid Injection	Plugged	481855.2	4278707.8
78	4708703769	Looney 38	Fluid Injection	Plugged	481908.2	4278884.7
79	4708703771	MJ Snodgrass 100	Fluid Injection	Plugged	481731.8	4279255.3
80	4708703772	MJ Snodgrass 101	Fluid Injection	Plugged	481876.3	4279061.9
81	4708703773	MJ Snodgrass 102	Fluid Injection	Plugged	482069.5	4279125.8
82	4708703774	Looney 40	Fluid Injection	Shut-In	481566.4	4279126.9
83	4708703775	Tallman 70	Fluid Injection	Shut-In	481889.7	4278449.3
84	4708703776	Tallman 71	Fluid Injection	Shut-In	481890.1	4278626.5
85	4708703777	Tallman 72	2R Oil Production	Plugged	482035.4	4278819.4
86	4708703778	Tallman 73	Fluid Injection	Shut-In	482180.5	4278899.6

87	4708703781	Looney 39	Fluid Injection	Shut-In	481621.0	4278864.0
88	4708703875	Looney 42	Fluid Injection	Shut-In	481435.8	4278385.9
89	4708703876	MJ Snodgrass 105	Fluid Injection	Plugged	481679.6	4279416.3
90	4708703877	Tallman 74	Fluid Injection	Plugged	482018.0	4278089.0
91	4708703878	Tallman 76	Fluid Injection	Shut-In	482147.6	4278561.5
92	4708703879	Tallman 75	Fluid Injection	Shut-In	482066.8	4278465.0
93	4708703880	Looney 41	Fluid Injection	Shut-In	481502.4	4279335.9
94	4708703968	Looney 47	2R Oil Production	Active Well	481549.3	4278723.9
95	4708703974	Looney 44	Fluid Injection	Plugged	481435.0	4278625.0
96	4708703976	Looney 46	Fluid Injection	Plugged	481298.0	4279125.0
97	4708703977	Looney 45	Fluid Injection	Plugged	481404.7	4278853.0
98	4708704013	Tallman 64	Fluid Injection	Shut-In	481160.3	4277629.7
99	4708704078	Looney 43	Fluid Injection	Shut-In	481298.0	4279125.0
100	4708704079	Looney 48	Fluid Injection	Plugged	481210.9	4278611.8
101	4708704080	Looney 49	Fluid Injection	Plugged	481243.6	4278821.1
102	4708704168	Looney 51	2R Oil Production	Active Well	481020.0	4278967.0
103	4708704172	Looney 50	Fluid Injection	Shut-In	481191.0	4279045.0
104	4708704421	200410	Gas Production	Active Well	481518.2	4279207.0
105	4708704623	MJ Snodgrass 813	Gas Production	Abandoned Well	482992.6	4279635.6
106	4708790804	Pre-1929 Unknown	Oil Production	Plugged	480952.5	4277018.2
107	4708790805	Pre-1929 Unknown	Oil Production	Plugged	480985.2	4277227.4
108	4708790806	Pre-1929 Unknown	Oil Production	Plugged	481194.4	4277178.6
109	4708790808	Pre-1929 Unknown	Oil Production	Plugged	481741.8	4277129
110	4708790809	Pre-1929 Unknown	Oil Production	Plugged	481999.7	4277241.2
111	4708790810	Pre-1929 Unknown	Oil Production	Plugged	481436.2	4277274.7
112	4708790811	Pre-1929 Unknown	Oil Production	Plugged	481645.6	4277338.6
113	4708790812	Pre-1929 Unknown	Oil Production	Plugged	481935.7	4277434.6
114	4708790818	Pre-1929 Unknown	Oil Production	Plugged	481162.6	4277372
115	4708790819	Pre-1929 Unknown	Oil Production	Plugged	481420.4	4277403.6
116	4708790820	Pre-1929 Unknown	Oil Production	Plugged	481372.5	4277580.8
117	4708790821	Pre-1929 Unknown	Oil Production	Plugged	481082.5	4277549.3
118	4708790822	Pre-1929 Unknown	Oil Production	Plugged	481630.1	4277596.3
119	4708790832	Pre-1929 Unknown	Oil Production	Plugged	481050.9	4277807.1
120	4708790833	Pre-1929 Unknown	Oil Production	Plugged	481083.6	4278016.4
121	4708790834	Pre-1929 Unknown	Oil Production	Plugged	481197	4278273.8
122	4708790835	Pre-1929 Unknown	Oil Production	Plugged	481485.6	4277757.7
123	4708790836	Pre-1929 Unknown	Oil Production	Plugged	481341	4277903
124	4708790837	Pre-1929 Unknown	Oil Production	Plugged	481389.8	4278128.4
125	4708790838	Pre-1929 Unknown	Oil Production	Plugged	481615.5	4278240.6
126	4708790843	Pre-1929 Unknown	Oil Production	Plugged	481937.6	4278288.2
127	4708790844	Pre-1929 Unknown	Oil Production	Plugged	482066.2	4278191.2
128	4708790848	Pre-1929 Unknown	Oil Production	Plugged	482453.4	4278544.7
129	4708790850	Pre-1929 Unknown	Oil Production	Plugged	482211.5	4278368.1
130	4708790851	Pre-1929 Unknown	Oil Production	Plugged	482002.6	4278513.5
131	4708790852	Pre-1929 Unknown	Oil Production	Plugged	482115.8	4278738.7
132	4708790853	Pre-1929 Unknown	Oil Production	Plugged	481680.4	4278433.7
133	4708790854	Pre-1929 Unknown	Oil Production	Plugged	481729.1	4278610.7

134	4708790855	Pre-1929 Unknown	Oil Production	Plugged	481858.2	4278755.4
135	4708790856	Pre-1929 Unknown	Oil Production	Plugged	481374.7	4278531
136	4708790857	Pre-1929 Unknown	Oil Production	Plugged	481632.9	4278820.3
137	4708790862	Pre-1929 Unknown	Oil Production	Plugged	480989.1	4278886.1
138	4708790863	Pre-1929 Unknown	Oil Production	Plugged	481246.5	4278805
139	4708790866	Pre-1929 Unknown	Oil Production	Plugged	482986.3	4279268.3
140	4708790868	Pre-1929 Unknown	Oil Production	Plugged	482825.1	4279155.9
141	4708790869	Pre-1929 Unknown	Oil Production	Plugged	482809.4	4279365.3
142	4708790874	Pre-1929 Unknown	Oil Production	Plugged	482584.2	4279430.2
143	4708790875	Pre-1929 Unknown	Oil Production	Plugged	482374.7	4279334
144	4708790876	Pre-1929 Unknown	Oil Production	Plugged	482438.7	4279156.7
145	4708790877	Pre-1929 Unknown	Oil Production	Plugged	482083.9	4278899.8
146	4708790878	Pre-1929 Unknown	Oil Production	Plugged	482245.2	4279044.4
147	4708790879	Pre-1929 Unknown	Oil Production	Plugged	482149	4279189.6
148	4708790880	Pre-1929 Unknown	Oil Production	Plugged	481923.3	4279077.3
149	4708790881	Pre-1929 Unknown	Oil Production	Plugged	481182.6	4279030.6
150	4708790882	Pre-1929 Unknown	Oil Production	Plugged	481456.3	4279013.9
151	4708790883	Pre-1929 Unknown	Oil Production	Plugged	481746.1	4279029.3
152	4708790887	Pre-1929 Unknown	Oil Production	Plugged	481633.9	4279255.1
153	4708790891	Pre-1929 Unknown	Oil Production	Plugged	481489.6	4279480.9
154	4708790892	Pre-1929 Unknown	Oil Production	Plugged	481747.2	4279496.4
155	4708790893	Pre-1929 Unknown	Oil Production	Plugged	481361.2	4279642.2
156	4708790894	Pre-1929 Unknown	Oil Production	Plugged	481634.8	4279641.6
157	4708790897	Pre-1929 Unknown	Oil Production	Plugged	481361.4	4279754.9
158	4708790898	Pre-1929 Unknown	Oil Production	Plugged	481506.4	4279770.7

Appendix F

Area Permit Wells - Injectors

Ground Resources, LLC
2R08700008AP
Tariff Field

	API No.	Well Name	Well Type	Well Status	Easting	Northing
1	4708700701	Looney 28	Fluid Injection	Shut-In	481656.0	4278648.0
2	4708702080	Tallman 54	Fluid Injection	Shut-In	481550.6	4277629.1
3	4708702405	Tallman 55	Fluid Injection	Shut-In	481849.0	4277612.0
4	4708702406	Tallman 56	Fluid Injection	Shut-In	481763.0	4277369.6
5	4708702407	Tallman 57	Fluid Injection	Shut-In	481558.3	4277327.8
6	4708702408	Tallman 58	Fluid Injection	Shut-In	481369.9	4277506.4
7	4708702409	Tallman 59	Fluid Injection	Shut-In	481337.3	4277597.0
8	4708702638	Looney 7	Fluid Injection	Shut-In	481742.0	4278369.0
9	4708702778	MJ Snodgrass 12	Fluid Injection	Shut-In	482826.1	4279392.6
10	4708702844	Tallman 40	Fluid Injection	Shut-In	482567.9	4279365.8
11	4708703096	Looney 18	Fluid Injection	Shut-In	481486.8	4279529.4
12	4708703604	Tallman 61	Fluid Injection	Shut-In	481870.8	4277883.6
13	4708703605	Tallman 62	Fluid Injection	Shut-In	481870.8	4277883.6
14	4708703608	Tallman 65	Fluid Injection	Shut-In	481227.5	4277766.9
15	4708703660	Looney 31	Fluid Injection	Shut-In	481758.5	4278368.1
16	4708703774	Looney 40	Fluid Injection	Shut-In	481566.4	4279126.9
17	4708703775	Tallman 70	Fluid Injection	Shut-In	481889.7	4278449.3
18	4708703776	Tallman 71	Fluid Injection	Shut-In	481890.1	4278626.5
19	4708703778	Tallman 73	Fluid Injection	Shut-In	482180.5	4278899.6
20	4708703781	Looney 39	Fluid Injection	Shut-In	481621.0	4278864.0
21	4708703875	Looney 42	Fluid Injection	Shut-In	481435.8	4278385.9
22	4708703878	Tallman 76	Fluid Injection	Shut-In	482147.6	4278561.5
23	4708703879	Tallman 75	Fluid Injection	Shut-In	482066.8	4278465.0
24	4708703880	Looney 41	Fluid Injection	Shut-In	481502.4	4279335.9
25	4708704013	Tallman 64	Fluid Injection	Shut-In	481160.3	4277629.7
26	4708704078	Looney 43	Fluid Injection	Shut-In	481298.0	4279125.0
27	4708704172	Looney 50	Fluid Injection	Shut-In	481191.0	4279045.0

APPENDIX D

Public Service District Affidavit

Underground Injection Control Permit applicants must identify all publically recorded drinking water sources within a one (1) mile radius of the proposed injection well facility. If no drinking water sources are present within this radius a written affidavit shall be supplied by the local Public Service District (PSD) as ample verification.

"I certify under penalty of law that (state name of business)

Ground Resources LLC.

has verified with the public service district (state name of PSD)

Clover PSD

that there are no such publically recorded sources.

Allen Jones

(Signature of Authorized Representative)

Sworn and subscribed to before me this 1 day of May, 2018.

Christina Trent, my commission expires May 1, 2018

(Notary Signature)

Christina Trent



APPENDIX E

Water Sources

Operator: GROUND RESOURCES, LLC Year 2017 UIC Permit # 2R08702AP

Water Source Name	Units	Source # 1	Source # 2	Source # 3	Source # 4
Northling		L. SNODGRASS	H. BOGGS	D. DEWESE	D. KEEN
Easting		422132.6	4279193.5	4280939.5	4278534.3
Parameter		481115.5	481890.3	482132.6	482392.6
TPH - GRO	mg/L				
TPH - DRO	mg/L				
TPH - ORO	mg/L				
BTEX	mg/L				
Chloride	mg/L	15.0	61.0	53.0	31.0
Sodium	mg/L				
Total Dissolved Solids (TDS)	mg/L	249 J	3.34 J	267 J	210 J
Aluminum	mg/L				
Arsenic	mg/L				
Barium	mg/L				
Iron	mg/L	.72	.58	.34	2.14
Manganese	mg/L				
pH	SU	8.1	8.2	8.2	7.8
Calcium	mg/L				
Sulfate	mg/L				
MBAS	mg/L	.11	.01	.01	NOT DETECTED
Dissolved Methane	mg/L				
Dissolved Ethane	mg/L				
Dissolved Butane	mg/L				
Dissolved Propane	mg/L				
Bacteria	c/100m				
(Total Coliform)	L				

TARIFF UIC PERMIT

SUBMITTED BY:
GROUND RESOURCES, LLC
DATE: 5/11/2018
Updated: 7/20/2020
USDW
LOCATIONS

Legend


USDW LOCATIONS

TARIFF FIELD BOUNDARY

.25 MILE AOR

1 MILE AOR

1 inch = 2,000 feet



Sources: Esri, HERE, Garmin, Intermap, increment P Corp., GEBCO, USGS, FAO, NPS, NRCAN, GeoBase, IGN, Kadaster NL, Ordnance Survey, Esri Japan, METI, Esri China (Hong Kong), swisstopo, © OpenStreetMap contributors, and the GIS User Community

PREPARED BY:
BLAKE JONES, GIS SPECIALIST
PRECISION OIL AND GAS, INC.

Sturm Environmental Services

JOHN W STURM, PRESIDENT

COMPANY: PRECISION OIL & GAS, INC.
SAMPLE ID: TARIFF USDW L. SNODGRASS
SAMPLED BY: B. JONES

DATE/TIME SAMPLED:* 11-29-17 1315
DATE/TIME RECEIVED: 11-30-17 1222
LABORATORY ID: POG 171130-1

PARAMETER	TEST RESULTS	UNITS	METHOD	METHOD DETECTION LIMIT	DATE/TIME ANALYZED	ANALYST
*FIELD pH	7.6	units			11-29-17 1315	BJ
*FIELD TEMP	54	°F			11-29-17 1315	BJ
pH O	8.1	units	SM 22 nd 4500 H B	.1	12-01-17 1540	KH
Fe	.72	mg/L	EPA 200.7 Rev 4.4-1994	.02	12-05-17 0745	DB
TDS	249 J	mg/L	SM22 nd 2540 C	4	12-04-17 1459	MRS
Cl ⁻	15.0	mg/L	EPA 300.0 Rev 2.1-1993	.50	12-04-17 2222	DC
MBAS	.11	mg/L	SM22 nd 5540C	.01	11-30-17 2350	SW

*Client Provided

**See Attached. The following results meet or exceed requirements and standards set forth by the certifying authority except where noted.

Data Qualifiers

- B Analyte found in reagent blank. Indicates possible reagent or background contamination.
- E Estimated Reported value exceeded calibration range.
- J Reported value is an estimate because concentration is less than reporting limit.
- PND Precision not determined.
- R Sample results rejected because of gross deficiencies in QC or method performance. Re-sampling and/or re-analysis is necessary.
- RND Recovery not determined.
- U Compound was analyzed for, but not detected.
- O Out of holding. Time does not meet 40 CFR 136/141 compliance.
- T This result is not supported by our certification ID.
- A Does not meet 40 CFR 136/141 compliance.
- C Does not meet 47 CSR 32 compliance.

Narrative:

Approved

Sturm Environmental Services

JOHN W. STURM, PRESIDENT

COMPANY: PRECISION OIL & GAS, INC.

DATE/TIME SAMPLED:* 11-29-17 1350

SAMPLE ID: TARIFF USDW H. BOGGS

DATE/TIME RECEIVED: 11-30-17 1222

SAMPLED BY: B. JONES

LABORATORY ID: POG 171130-2

PARAMETER	TEST RESULTS	UNITS	METHOD	METHOD DETECTION LIMIT	DATE/TIME ANALYZED	ANALYST
*FIELD pH	7.4	units			11-29-17 1350	BJ
*FIELD TEMP	50	°F			11-29-17 1350	BJ
pH O	8.2	units	SM 22 nd 4500 H B	.1	12-01-17 1540	KH
Fe	.58	mg/L	EPA 200.7 Rev 4.4-1994	.02	12-05-17 0745	DB
TDS	3.34 J	mg/L	SM22 nd 2540 C	4	12-04-17 1459	MRE
Cl ⁻	61.0	mg/L	EPA 300.0 Rev 2.1-1993	.50	12-04-17 2222	DC
MBAS	.01	mg/L	SM22 nd 5540C	.01	11-30-17 2350	SW

*Client Provided

**See Attached. The following results meet or exceed requirements and standards set forth by the certifying authority except where noted.

Data Qualifiers

- B Analyte found in reagent blank. Indicates possible reagent or background contamination.
- E Estimated Reported value exceeded calibration range.
- J Reported value is an estimate because concentration is less than reporting limit.
- PND Precision not determined.
- R Sample results rejected because of gross deficiencies in QC or method performance. Re-sampling and/or re-analysis is necessary.
- RND Recovery not determined.
- U Compound was analyzed for, but not detected.
- O Out of holding. Time does not meet 40 CFR 136/141 compliance.
- T This result is not supported by our certification ID.
- A Does not meet 40 CFR 136/141 compliance.
- C Does not meet 47 CSR 32 compliance.

Narrative:

Approved _____

JOHN W. STURM, PRESIDENT

DATE/TIME SAMPLED:* 11-29-17 1434

DATE/TIME RECEIVED: 11-30-17 1222

LABORATORY ID: POG 171130-3

*Client Provided

Data Qualifiers

Estimated Reported value exceeded calibration range.

PND Precision not determined.

RND Simple results rejected or
Recovery not determined.

Out of holding. Time does not meet 40 CFR 136/141 compliance.

Does not meet 40 CFR 136/141 compliance.

C Does not meet 47 CSR 32 compliance.

Narrative:

Approved _____

Sturm Environmental Services

JOHN W. STURM, PRESIDENT

COMPANY: PRECISION OIL & GAS, INC.

DATE/TIME SAMPLED:* 11-29-17 1530

SAMPLE ID: TARIFF USDW D. KEEN

DATE/TIME RECEIVED: 11-30-17 1222

SAMPLED BY: B. JONES

LABORATORY ID: POG 171130-4

PARAMETER	TEST RESULTS	UNITS	METHOD	METHOD DETECTION LIMIT	DATE/TIME ANALYZED	ANALYST
*FIELD pH	6.7	units			11-29-17 1530	BJ
*FIELD TEMP	5.6	°F			11-29-17 1530	BJ
pH O	7.8	units	SM 22 nd 4500 H B	.1	12-01-17 1540	KH
Fe	2.14	mg/L	EPA 200.7 Rev 4.4-1994	.02	12-05-17 0745	DB
TDS	210 J	mg/L	SM22 nd 2540 C	4	12-04-17 1459	MRS
Cl ⁻	31.0	mg/L	EPA 300.0 Rev 2.1-1993	.50	12-04-17 2222	DC
MBAS	U	mg/L	SM22 nd 5540C	.01	11-30-17 2350	SW

*Client Provided

**See Attached. The following results meet or exceed requirements and standards set forth by the certifying authority except where noted.

Data Qualifiers

- B Analyte found in reagent blank. Indicates possible reagent or background contamination.
- E Estimated Reported value exceeded calibration range.
- J Reported value is an estimate because concentration is less than reporting limit.
- PND Precision not determined.
- R Sample results rejected because of gross deficiencies in QC or method performance. Re-sampling and/or re-analysis is necessary.
- RND Recovery not determined.
- U Compound was analyzed for, but not detected.
- O Out of holding. Time does not meet 40 CFR 136/141 compliance.
- T This result is not supported by our certification ID.
- A Does not meet 40 CFR 136/141 compliance.
- C Does not meet 47 CSR 32 compliance.

Narrative:

Approved

Doyle G. Jones

Section 8

Geological Data

Section 8

Geologic Information

Historical references indicate that the Tariff Field was first drilled in 1909. Primary production occurred between 1910 and 1950. Secondary recovery injection using gas began 1951. Secondary recovery injection using water began in 1978 and was expanded in 1983.

Injection Zone

The injection zone within the Tariff Field is the Big Injun Sandstone, a member of the Greenbrier Group of Mississippian age. It ranges in depth from 1,900 to 2,180 feet averaging 2,098 feet and ranges in thickness from 17 to 40 feet averaging 28 feet. Porosity ranges from 13.6% to 22.2% averaging 17.2%. Permeability ranges up to 20md. It is described as a light gray to green, moderate to well sorted, fine to medium grained, subangular, argillaceous sandstone. It is cemented with calcite and/or dolomite and displays varying degrees of friability depending on the degree of cementation. The reservoir is bounded by a pinch-out on the north and east and by a gas cap on the south and west.

Confining Zone


The confining zone within the Tariff Field is the Greenbrier Limestone (Big Lime). Like the Big Injun Sandstone, it is a member of the Greenbrier Group of Mississippian age. It ranges in depth from 1,795 to 2,072 feet averaging 1,971 feet and ranges in thickness from 70 to 115 feet averaging 105 feet. In several of the drill records a secondary confining zone identified below the Greenbrier Limestone as the Keener Sandstone, a dense dolomitic unit also identified as the Loyalhanna Dolomite. This unit occurs sporadically but may be over 70 feet in thickness. The Big Injun injection zone is underlain by the Pocono Shale.

Local Structural Geology

There are no known faults within the Tariff Field. The geologic structure within the field is dominated by the Robinson syncline with an axis trending North-Northeast and South-Southwest extending through the eastern half of the field plunging North-Northeast at approximately 30 feet per mile. Dip toward the syncline axis is approximately 45 feet per mile.


Statement of Seismic Risk

West Virginia, in general has a low seismic risk. There is no record of any earthquakes within the Tariff Field. According to WVGES records, the closest earthquake occurred 13 miles east in Braxton County on January 10, 2012 with a magnitude of 2.8. According to USGS data, the probability of an earthquake occurring in the local area of Tariff Field is 1% over the next 50 years.





This publication represents interpretations of best available data made by professional geologists and geographers. As in all research work, professional interpretations may vary, and can change with advancements in both technology and data quality. This publication is offered as a service of the State of West Virginia; proper use of the information herein is the sole responsibility of the user.

Map Date: January 26, 2016
Projection: Transverse Mercator
Horizontal Datum: NAD 1983
Coordinate System: UTMz17n
Map scale for full
3.5" x 11" display: 1:2,000,000



Recorded instrumental and reported historic (non-instrumental or felt) earthquake epicenters and magnitudes for West Virginia. Data were compiled from several earthquake catalog sources.

87, 2011, 2.7



**West Virginia Geological
and Economic Survey**
Mont Chateau Research Center
1 Mont Chateau Road
Morgantown, WV 26508-8079
Phone: (304) 594-2331
www.wvgs.wvnet.edu

Event Num	WPMR	County	UTC Year	UTC Month	UTC Day	UTC HH	UTC MM	UTC SS	Latitude (N)	Longitude (W)	Magnitude (M)	Recorded	MW	Magnitude Type	USGS Link
1	18240715160	Wood	1824	7	15	16	20	0.00	39.70000	-80.50000	4.1	Historic	4.0	Mb	VTSO NCEER
2	18461019020	Jefferson	1846	10	19	2	0	0.00	39.30000	-77.90000	2.7	Historic	3.0	<NULL>	VTSO <NULL>
3	18530502140	Pendleton	1853	5	2	14	20	0.00	38.50000	-79.50000	4.4	Historic	5.5	<NULL>	NCEER Wheeler 1-2737
4	19090402070	Berkeley	1909	4	2	7	25	0.00	39.40000	-78.00000	3.6	Historic	5.0	Mb	VTSO Wheeler 1-2737
5	19330615010	Mingo	1933	6	15	1	14	36.80	37.56800	-81.97300	0.0	Historic	0.0	<NULL>	VTSO <NULL>
6	19351101080	Hardy	1935	11	1	8	30	0.00	38.90000	-78.90000	3.3	Historic	4.0	<NULL>	VTSO NCEER
7	19570307210	Monongalia	1957	3	7	21	5	9.00	39.60000	-79.90000	2.9	Historic	3.0	Mb	VTSO <NULL>
8	19570313210	Monongalia	1957	3	13	21	0	41.00	39.60000	-79.90000	2.9	Historic	3.0	Mb	VTSO <NULL>
9	19631010000	Morgan	1963	10	10	0	0	0.00	39.65000	-78.19700	3.6	Historic	0.0	<NULL>	Wheeler 1-2737
10	19641125020	McDowell	1964	11	25	2	50	5.00	37.40000	-81.50000	4.5	Instrumental	0.0	Mb	<NULL>
11	19650426150	McDowell	1965	4	26	15	26	19.70	37.32500	-81.60200	3.5	Instrumental	0.0	Mblg	VTSO NCEER
12	19660928000	Harrison	1966	9	28	0	0	0.00	39.30000	-80.30000	3.1	Instrumental	4.0	<NULL>	NCEER <NULL>
13	19671216120	McDowell	1967	12	16	12	23	33.40	37.36000	-81.60400	3.5	Instrumental	0.0	Mb	VTSO NCEER
14	19691120010	Mercer	1969	11	20	1	0	9.30	37.44900	-80.93200	4.6	Instrumental	6.0	Mblg	VTSO NCEER
15	19700811060	Lincoln	1970	8	11	6	14	25.50	38.23000	-82.05000	2.8	Instrumental	4.0	Mblg	VTSO NCEER
16	19710401050	McDowell	1971	4	1	5	5	11.00	37.40000	-81.60000	3.0	Instrumental	0.0	Mb	NCEER ANSS
17	19720109230	McDowell	1972	1	9	23	24	29.00	37.40000	-81.60000	3.7	Instrumental	0.0	Mblg	NCEER ANSS
18	19720912150	Monongalia	1972	9	12	15	17	13.70	39.60000	-79.90000	2.9	Historic	3.0	Mb	VTSO NCEER
19	19741020150	Wood	1974	10	20	15	13	55.60	39.06000	-81.60900	3.8	Instrumental	5.0	Mb	VTSO NCEER
20	19760130180	Morgan	1976	1	30	18	58	49.80	39.68300	-78.17000	2.8	Instrumental	0.0	Lg	USGS Further Info
21	19760506180	Monongalia	1976	5	6	18	46	8.10	39.60000	-79.90000	3.1	Historic	4.0	Mb	VTSO NCEER
22	19760619050	McDowell	1976	6	19	5	54	13.40	37.34400	-81.60200	4.7	Instrumental	5.0	Mb	VTSO NCEER
23	19760703200	Mercer	1976	7	3	20	53	45.80	37.32000	-81.13000	2.7	Instrumental	0.0	Mblg	VTSO <NULL>
24	19780814040	Fayette	1978	8	14	4	50	5.40	37.93900	-80.87400	1.6	Instrumental	0.0	Mc	VTSO ANSS
25	19790916090	Poehontas	1979	9	16	9	39	22.60	38.09900	-80.24000	1.6	Instrumental	0.0	Mc	ANSS <NULL>
26	19790919000	Poehontas	1979	9	19	0	45	57.40	38.11000	-80.24300	2.0	Instrumental	0.0	Mc	ANSS <NULL>
27	19791031080	Raleigh	1979	10	31	8	32	47.30	37.61700	-81.20700	0.8	Instrumental	0.0	Mc	ANSS <NULL>
28	19800410220	Mercer	1980	4	10	22	33	15.70	37.48700	-81.08600	0.7	Instrumental	0.0	Mc	VTSO ANSS
29	19800921100	Poehontas	1980	9	21	10	2	46.30	38.17500	-80.07000	1.4	Instrumental	0.0	Mc	VTSO ANSS
30	19801016030	Poehontas	1980	10	16	3	48	7.60	38.06600	-80.21500	1.1	Instrumental	0.0	Mc	VTSO ANSS
31	19801105210	Poehontas	1980	11	5	21	48	14.20	38.18800	-79.93600	3.0	Instrumental	0.0	Ml	ANSS <NULL>
32	19801125070	Poehontas	1980	11	25	7	44	4.00	38.09500	-80.12300	0.6	Instrumental	0.0	Md	VTSO ANSS
33	19811130170	Mingo	1981	11	30	17	33	11.00	37.63000	-82.20000	2.5	Instrumental	0.0	Md	VTSO ANSS
34	19820623160	Fayette	1982	6	23	16	17	34.10	37.87000	-80.95700	2.5	Instrumental	0.0	Md	VTSO ANSS
35	19830121050	Poehontas	1983	1	21	5	33	20.40	38.06700	-80.14400	0.4	Instrumental	0.0	Md	VTSO ANSS
36	19830526010	Monroe	1983	5	26	1	4	44.80	37.30600	-80.31600	2.2	Instrumental	0.0	Md	VTSO ANSS
37	19830610000	Greenbrier	1983	6	10	0	18	40.40	37.94800	-80.16300	1.2	Instrumental	0.0	Md	VTSO ANSS
38	19830610001	Greenbrier	1983	6	10	0	24	57.00	37.95100	-80.18900	1.2	Instrumental	0.0	Md	VTSO ANSS
39	19830610002	Greenbrier	1983	6	10	0	31	8.30	37.93800	-80.16800	0.4	Instrumental	0.0	Md	VTSO ANSS
40	19830720040	Greenbrier	1983	7	20	4	41	40.90	37.88500	-80.69100	1.6	Instrumental	0.0	Md	VTSO ANSS
41	19830725030	Wyoming	1983	7	25	3	27	0.20	37.49600	-81.35200	0.6	Instrumental	0.0	Md	VTSO ANSS
42	19831113160	Summers	1983	11	13	16	51	6.70	37.55600	-80.77500	0.4	Instrumental	0.0	Md	VTSO ANSS
43	19831113170	Monroe	1983	11	13	17	50	50.10	37.55900	-80.75300	0.7	Instrumental	0.0	Md	VTSO ANSS
44	19831125160	Monroe	1983	11	25	16	27	47.80	37.56800	-80.74500	0.7	Instrumental	0.0	Md	VTSO <NULL>
45	19831223100	Summers	1983	12	23	10	51	21.90	37.76600	-80.83700	0.3	Instrumental	0.0	Md	VTSO ANSS
46	19840202050	Mingo	1984	2	2	5	10	19.70	37.71700	-82.21800	1.9	Instrumental	0.0	Md	VTSO ANSS
47	19840311040	Summers	1984	3	11	4	1	38.90	37.47400	-80.90000	1.1	Instrumental	0.0	Md	VTSO ANSS
48	19841009050	Summers	1984	10	9	5	33	31.50	37.71300	-80.89100	2.1	Instrumental	0.0	Md	VTSO ANSS
49	19841221130	Poehontas	1984	12	21	13	12	21.90	38.19800	-80.20800	1.6	Instrumental	0.0	Md	VTSO ANSS
50	19850614070	Mercer	1985	6	14	7	57	10.20	37.53400	-81.02000	0.8	Instrumental	0.0	Md	VTSO ANSS
51	19860226210	Pendleton	1986	2	26	21	53	20.80	38.50700	-79.29200	2.3	Instrumental	0.0	Md	VTSO ANSS
52	19861220080	Greenbrier	1986	12	20	8	13	12.80	38.05800	-80.64300	1.2	Instrumental	0.0	Md	VTSO ANSS
53	19890319100	Logan	1989	3	19	10	7	55.80	37.73500	-82.06400	1.9	Instrumental	0.0	Md	VTSO ANSS
54	19910422010	Greenbrier	1991	4	22	1	1	20.20	37.94200	-80.20500	3.5	Instrumental	0.0	Md	VTSO Further Info

USGS ID	USGS Name	USGS Address	USGS City	USGS State	USGS Zip	USGS Phone	USGS Fax	USGS Email	USGS Website	USGS Notes	USGS Status	USGS Type	USGS Category	USGS Subcategory	USGS Parent	USGS Child	USGS Grandchild	USGS Great-grandchild	USGS Further Info
53	19970628180	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
56	19970629100	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
57	19970630070	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
58	19970631000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
59	19970632000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
60	19970633000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
61	19970634000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
62	19970635000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
63	19970636000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
64	19970637000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
65	19970638000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
66	19970639000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
67	19970640000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
68	19970641000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
69	19970642000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
70	19970643000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
71	19970644000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
72	19970645000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
73	19970646000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
74	19970647000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
75	19970648000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
76	19970649000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
77	19970650000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
78	19970651000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
79	19970652000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
80	19970653000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
81	19970654000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
82	19970655000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
83	19970656000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
84	19970657000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
85	19970658000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
86	19970659000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
87	19970660000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
88	19970661000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
89	19970662000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
90	19970663000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
91	19970664000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
92	19970665000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
93	19970666000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
94	19970667000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
95	19970668000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
96	19970669000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS
97	19970670000	Kanawha	1997	6	28	18	34	55.50	38.29106	-81.34500	1.0	Instrumental	USGS	USGS	USGS	USGS	USGS	USGS	USGS

Data as of January 26, 2015. For a more detailed listing, please download the West Virginia Earthquake spreadsheet from USGS at <http://www.wvgs.net/earthquake/earthquake.html>. If you view the map and data as a PDF, you can click any of the blue hyperlinked text to view further information on a web site. Please note that USGS links, above, are considered "beta" at the time of this publication and USGS may change destinations, pages, etc. afterward.

Definition of terms on next page.



2081

Log Analysis

Schlumberger

COMPANY PENNZOIL COMPANY			WELL P. A. TALLMAN #54		
FIELD SMITHFIELD		COUNTY ROANE	STATE W. VA.		
DEPTH	R	$\frac{RW}{RT}$	% POROSITY	% WATER	REMARKS
2142-44	12	.065	16	41	pMA=2.68
2144-46	13	.062	17	36	RW=0.05
2146-48	16	.056	20	28	
2148-50	15	.056	25	22	
2150-52	13	.053	22	28	
2152-54	11	.057	21	32	
2154-56	12	.065	20	33	
2156-58	14	.060	22	27	
2158-60	15	.056	18	31	
2160-62	15	.056	20	28	
2162-64	15	.056	19	29	
2164-66	15	.056	21	27	
2166-68	13	.062	21	30	
2168-70	14	.060	18	33	
2170-72	14	.060	0	67	
2172-74	10	NOTE: MEDIUM INDUCTION VALUE USED AT THIS DEPTH AS IT IS BELOW THE FR OF THE DEEP INDUCTION			13 54
AVG 13.6					
SW= 1 RW= RT					
pMA= .00 pMA= .00					

All interpretations are opinions based on inferences from electrical and other measurements and we cannot, and do not, guarantee the accuracy or correctness of any interpretations, and we shall not, except in the case of gross or willful negligence on our part, be liable or responsible for any loss, costs, damages or expenses incurred or sustained by anyone resulting from any interpretation made by any of our officers, agents or employees. These interpretations are also subject to Clause 4 of our General Terms and Conditions as set out in our current Price Schedule.

DATE **10/16/77** LOCATION **FAIRMONT** ENGINEER **HARGREAVES**

SW-1329-D

2406

Pag Analysis

1000

[illegible]


3604

McCullough

GAMMA RAY LOG

FILING NO.		COMPANY		PENNZOIL COMPANY	
PERMIT #		WELL		P. A. TALLMAN #61	
47-087-3604		FIELD		TARIFF	
COUNTY		ROANE		STATE	
LOCATION		DISTRICT: SMITHFIELD		OTHER SERVICES:	
		WATERSHED: SYCAMORE FORK		PERF.	
		TARIFF QUAD 7.5			
SEC.		TWP.		RGE.	
PERMANENT DATUM		GROUND LEVEL		ELEV. 1058'	
LOG MEASURED FROM		6' ABOVE GROUND LEVEL		KB 1053'	
DRILLING MEASURED FROM		E.B.		DF 1053'	
DATE		11-4-82		GL 1058'	
RUN NO.		ONE			
TYPE LOG		GAMMA RAY			
DEPTH - DRILLER		2157'			
DEPTH - LOGGER		2119'			
BOTTOM LOGGED INTERVAL		2116'			
TOP LOGGED INTERVAL		1800'			
TYPE FLUID IN HOLE		DRY			
SALINITY PPM CL		-			
DENSITY LB./GAL.		-			
LEVEL		-			
MAX. REC. TEMP. DEG. F.		-			
OPR. RIG TIME		1 HOUR			
RECORDED BY		SMITH			
WITNESSED BY		MR. GREENLEYS			
DISTRICT:		CHARLESTON			
Bore Hole Record		Casing Record			
NO.	BIT	FROM	TO	SIZE	WT.
ONE				8 5/8"	330
				45"	330
					T.D.

RUN NO.		ONE		TOOL MODEL NO.		5548-0-2		DIAM.		3.5"		DETECT. MODEL NO.		5548-25		TYPE		RCINT.		LENGTH		3"		DIST. TO N. SOURCE			
HOIST TRUCK NO.		1353		INST. TRUCK NO.		1353		TOOL SERIAL NO.		203334		LOG TICKET NO.															
GENERAL		GAMMA RAY		NEUTRON																							
RUN NO.		ONE		TOOL MODEL NO.		5548-0-2		DIAM.		3.5"		DETECT. MODEL NO.		5548-25		TYPE		RCINT.		LENGTH		3"		DIST. TO N. SOURCE			
HOIST TRUCK NO.		1353		INST. TRUCK NO.		1353		TOOL SERIAL NO.		203334		LOG TICKET NO.															
GENERAL		GAMMA RAY		NEUTRON																							
RUN NO.		ONE		TOOL MODEL NO.		5548-0-2		DIAM.		3.5"		DETECT. MODEL NO.		5548-25		TYPE		RCINT.		LENGTH		3"		DIST. TO N. SOURCE			
HOIST TRUCK NO.		1353		INST. TRUCK NO.		1353		TOOL SERIAL NO.		203334		LOG TICKET NO.															
GENERAL		GAMMA RAY		NEUTRON																							
RUN NO.		ONE		TOOL MODEL NO.		5548-0-2		DIAM.		3.5"		DETECT. MODEL NO.		5548-25		TYPE		RCINT.		LENGTH		3"		DIST. TO N. SOURCE			
HOIST TRUCK NO.		1353		INST. TRUCK NO.		1353		TOOL SERIAL NO.		203334		LOG TICKET NO.															
GENERAL		GAMMA RAY		NEUTRON																							
RUN NO.		ONE		TOOL MODEL NO.		5548-0-2		DIAM.		3.5"		DETECT. MODEL NO.		5548-25		TYPE		RCINT.		LENGTH		3"		DIST. TO N. SOURCE			
HOIST TRUCK NO.		1353		INST. TRUCK NO.		1353		TOOL SERIAL NO.		203334		LOG TICKET NO.															
GENERAL		GAMMA RAY		NEUTRON																							
RUN NO.		ONE		TOOL MODEL NO.		5548-0-2		DIAM.		3.5"		DETECT. MODEL NO.		5548-25		TYPE		RCINT.		LENGTH		3"		DIST. TO N. SOURCE			
HOIST TRUCK NO.		1353		INST. TRUCK NO.		1353		TOOL SERIAL NO.		203334		LOG TICKET NO.															
GENERAL		GAMMA RAY		NEUTRON																							
RUN NO.		ONE		TOOL MODEL NO.		5548-0-2		DIAM.		3.5"		DETECT. MODEL NO.		5548-25		TYPE		RCINT.		LENGTH		3"		DIST. TO N. SOURCE			
HOIST TRUCK NO.		1353		INST. TRUCK NO.		1353		TOOL SERIAL NO.		203334		LOG TICKET NO.															
GENERAL		GAMMA RAY		NEUTRON																							
RUN NO.		ONE		TOOL MODEL NO.		5548-0-2		DIAM.		3.5"		DETECT. MODEL NO.		5548-25		TYPE		RCINT.		LENGTH		3"		DIST. TO N. SOURCE			
HOIST TRUCK NO.		1353		INST. TRUCK NO.		1353		TOOL SERIAL NO.		203334		LOG TICKET NO.															
GENERAL		GAMMA RAY		NEUTRON																							
RUN NO.		ONE		TOOL MODEL NO.		5548-0-2		DIAM.		3.5"		DETECT. MODEL NO.		5548-25		TYPE		RCINT.		LENGTH		3"		DIST. TO N. SOURCE			
HOIST TRUCK NO.		1353		INST. TRUCK NO.		1353		TOOL SERIAL NO.		203334		LOG TICKET NO.															
GENERAL		GAMMA RAY		NEUTRON																							
RUN NO.		ONE		TOOL MODEL NO.		5548-0-2		DIAM.		3.5"		DETECT. MODEL NO.		5548-25		TYPE		RCINT.		LENGTH		3"		DIST. TO N. SOURCE			
HOIST TRUCK NO.		1353		INST. TRUCK NO.		1353		TOOL SERIAL NO.		203334		LOG TICKET NO.															
GENERAL		GAMMA RAY		NEUTRON																							
RUN NO.		ONE		TOOL MODEL NO.		5548-0-2		DIAM.		3.5"		DETECT. MODEL NO.		5548-25		TYPE		RCINT.		LENGTH		3"		DIST. TO N. SOURCE			
HOIST TRUCK NO.		1353		INST. TRUCK NO.		1353		TOOL SERIAL NO.		203334		LOG TICKET NO.															
GENERAL		GAMMA RAY		NEUTRON																							
RUN NO.		ONE		TOOL MODEL NO.		5548-0-2		DIAM.		3.5"		DETECT. MODEL NO.		5548-25		TYPE		RCINT.		LENGTH		3"		DIST. TO N. SOURCE			
HOIST TRUCK NO.		1353		INST. TRUCK NO.		1353		TOOL SERIAL NO.		203334		LOG TICKET NO.															
GENERAL		GAMMA RAY		NEUTRON																							
RUN NO.		ONE		TOOL MODEL NO.		5548-0-2		DIAM.		3.5"		DETECT. MODEL NO.		5548-25		TYPE		RCINT.		LENGTH		3"		DIST. TO N. SOURCE			
HOIST TRUCK NO.		1353		INST. TRUCK NO.		1353		TOOL SERIAL NO.		203334		LOG TICKET NO.															
GENERAL		GAMMA RAY		NEUTRON																							
RUN NO.		ONE		TOOL MODEL NO.		5548-0-2		DIAM.		3.5"		DETECT. MODEL NO.		5548-25		TYPE		RCINT.		LENGTH		3"		DIST. TO N. SOURCE			
HOIST TRUCK NO.		1353		INST. TRUCK NO.		1353		TOOL SERIAL NO.		203334		LOG TICKET NO.															
GENERAL		GAMMA RAY		NEUTRON																							
RUN NO.		ONE		TOOL MODEL NO.		5548-0-2		DIAM.		3.5"		DETECT. MODEL NO.		5548-25		TYPE		RCINT.		LENGTH		3"		DIST. TO N. SOURCE			
HOIST TRUCK NO.		1353		INST. TRUCK NO.		1353		TOOL SERIAL NO.		203334		LOG TICKET NO.															
GENERAL		GAMMA RAY		NEUTRON																							
RUN NO.		ONE		TOOL MODEL NO.		5548-0-2		DIAM.		3.5"		DETECT. MODEL NO.		5548-25		TYPE		RCINT.		LENGTH		3"		DIST. TO N. SOURCE			
HOIST TRUCK NO.		1353		INST. TRUCK NO.		1353		TOOL SERIAL NO.		203334		LOG TICKET NO.															
GENERAL		GAMMA RAY		NEUTRON																							
RUN NO.		ONE		TOOL MODEL NO.		5548-0-2		DIAM.		3.5"		DETECT. MODEL NO.		5548-25		TYPE		RCINT.		LENGTH		3"		DIST. TO N. SOURCE			
HOIST TRUCK NO.		1353		INST. TRUCK NO.		1353		TOOL SERIAL NO.		203334		LOG TICKET NO.															
GENERAL		GAMMA RAY		NEUTRON																							
RUN NO.		ONE		TOOL MODEL NO.		5548-0-2		DIAM.		3.5"		DETECT. MODEL NO.		5548-25		TYPE		RCINT.		LENGTH		3"		DIST. TO N. SOURCE			
HOIST TRUCK NO.		1353		INST. TRUCK NO.		1353		TOOL SERIAL NO.		203334		LOG TICKET NO.															
GENERAL		GAMMA RAY		NEUTRON																							
RUN NO.		ONE		TOOL MODEL NO.		5548-0-2		DIAM.		3.5"		DETECT. MODEL NO.		5548-25		TYPE		RCINT.		LENGTH		3"		DIST. TO N. SOURCE			
HOIST TRUCK NO.		1353		INST. TRUCK NO.		1353		TOOL SERIAL NO.		203334		LOG TICKET NO.															
GENERAL		GAMMA RAY		NEUTRON																							
RUN NO.		ONE		TOOL MODEL NO.		5548-0-2		DIAM.		3.5"		DETECT. MODEL NO.		5548-25		TYPE		RCINT.		LENGTH		3"		DIST. TO N. SOURCE			
HOIST TRUCK NO.		1353		INST. TRUCK NO.		1353		TOOL SERIAL NO.		203334		LOG TICKET NO.															
GENERAL		GAMMA RAY		NEUTRON																							
RUN NO.		ONE		TOOL MODEL NO.		5548-0-2		DIAM.		3.5"		DETECT. MODEL NO.		5548-25		TYPE		RCINT.		LENGTH		3"		DIST. TO N. SOURCE			
HOIST TRUCK NO.		1353		INST. TRUCK NO.		1353		TOOL SERIAL NO.		203334		LOG TICKET NO.															
GENERAL		GAMMA RAY		NEUTRON																							
RUN NO.		ONE		TOOL MODEL NO.		5548-0-2		DIAM.		3.5"		DETECT. MODEL NO.		5548-25		TYPE		RCINT.		LENGTH		3"		DIST. TO N. SOURCE			
HOIST TRUCK NO.		1353		INST. TRUCK NO.		1353		TOOL SERIAL NO.		203334		LOG TICKET NO.															
GENERAL		GAMMA RAY		NEUTRON																							
RUN NO.		ONE		TOOL MODEL NO.		5548-0-2		DIAM.		3.5"		DETECT. MODEL NO.		5548-25		TYPE		RCINT.		LENGTH		3"		DIST. TO N. SOURCE			
HOIST TRUCK NO.		1353		INST. TRUCK NO.		1353		TOOL SERIAL NO.		203334		LOG TICKET NO.															
GENERAL		GAMMA RAY		NEUTRON																							
RUN NO.		ONE		TOOL MODEL NO.		5548-0-2		DIAM.		3.5"		DETECT. MODEL NO.		5548-25		TYPE		RCINT.		LENGTH		3"					



2000

BIG LIME
CONFINING

2000' - 2085' (18' H.L.P.)

BIG MUON
INJECTION

2100

2116'
2119'

REPEAT SECTION
(CORRECTED)

CORRECTION

CORRECTION

WEST VIRGINIA
GEOLOGICAL AND ECONOMIC SURVEY



1 Mont Chateau Road
Morgantown, WV 26508-8079

Phone: (304) 594-2331

Fax: (304) 594-2575

Web: www.wvges.org

C. Edward Gaunch, *Commerce Cabinet Secretary*
B. Mitchel Blake, Jr., *Director and State Geologist*



August 20, 2020

IN REPLY, REFER TO:

Andrew Lockwood
Geologist III
WV Department of Environmental Protection
Office of Oil and Gas
601 57th Street
Charleston, WV 25304

OG/8999/0047/233/2020

Mr. Lockwood:

I have received the UIC permit (2R8700008AP) request submitted by Ground Resources, LLC requesting permission to initiate secondary recovery operations in the Tariff field, located in northern Roane County.

The Tariff field is nearly bisected by an unnamed syncline that trends in a southwestern to northeastern direction across the field (figure 1). The Arches Fork Anticline is located west of the field and an unnamed anticline is located to the southeast of the field. No known major fault systems exist in close proximity to the field. Located less than 20 miles from the southernmost extent of the Burning Spring Anticline and eastern edge of the Rome Through, some minor seismicity in the Precambrian basement rock can be expected. No known earthquakes have occurred in the Tariff field, with the closest being 13 miles to the east of the field.

The Permit application clearly defines the injection target Big Injun and the overlying Big Lime as the vertical confining zone. There is some concern as there is no mention of how the injected water flood will be contained laterally and to what extent lateral migration may occur. The depths provided in the application for the tops of the Big Injun and Big Lime in the Tariff field are consistent to those in the WVGES oil and gas database. The Big Injun structural top provided in the permit (figure 1 on page 29) is of poor quality and should be provided in higher resolution.

Production from the Big Injun in the Tariff field has been heavy with a large number of existing wells. Included in this are a large number of legacy wells (186) in which little to no information exists (figure 2). Communication between existing wells not included in this project may occur and should be taken into consideration.

The high porosity values provided in the log analysis of this permit along with the known lithology, and structure of the Tariff field appears to be highly conducive for a successful enhanced oil recovery venture

I hope this review helps you with the permitting process. If you have any questions, please feel free to contact me for further information.

Sincerely,

A handwritten signature in blue ink, reading "Gary W. Daft". The signature is fluid and cursive, with the first name "Gary" being the most prominent.

Gary Daft
Geologist III
Oil and Gas Section
gdaft@geosrv.wvnet.edu

Figure1.





Figure 2.



Section 9

Operating Requirements

Section 9

Operating Requirements

1. All proposed operating data is provided in the attached Appendix A forms.
2. There are no brine disposal wells included in this application.
3. The injection fluid is produced water from the Tariff Field. An analysis is attached in this application.
4. No additives will be used at this time.
5. The annulus fluid will be fresh water used to conduct the MIT.
6. Initially only those wells with a tubing and packer system will be used for injection. Additional shut-in wells will be brought online as they are rehabilitated.
7. Only wells with valid MITs for both the well and the injection pipeline will be allowed to operate.

Injectate Analysis

November 27, 2019

Missy Hoops
STURM ENVIRONMENTAL SERVICES
P O BOX 650
Bridgeport, WV 26330


RE: Project: 19230
Pace Project No.: 739155
PRECISION OIL & GAS, INC.

Dear Missy Hoops:

Enclosed are the analytical results for sample(s) received by the laboratory on November 22, 2019. The results relate only to the samples included in this report. Results reported herein conform to the most current, applicable TNI/NELAC standards and the laboratory's Quality Assurance Manual, where applicable, unless otherwise noted in the body of the report.

If you have any questions concerning this report, please feel free to contact me.

Sincerely,



Todd Crone
todd.crone@pacelabs.com
800-999-0105
Project Manager

Enclosures



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC



Pace Analytical Services, LLC
225 Industrial Park RD
Beaver, WV 25813
(800)999-0105

CERTIFICATIONS

PRECISION OIL & GAS, INC.

Project: 19230

Pace Project No.: 739155

Pace Analytical Services Beaver

225 Industrial Park Drive, Beaver, WV 25813

Virginia VELAP 460148

Virginia DCLS 00281

West Virginia DEP 060

West Virginia DHHR 00412CM

North Carolina DEQ 466

Kentucky Wastewater Certification KY90039

Pennsylvania DEP 68-00839

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC



Pace Analytical Services, LLC
225 Industrial Park RD
Beaver, WV 25813
(800)989-0105

SAMPLE SUMMARY

PRECISION OIL & GAS, INC.

Project: 19230

Pace Project No.: 739155

Lab ID	Sample ID	Matrix	Date Collected	Date Received
739155001	19230	Water	11/19/19 08:00	11/22/19 17:30

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC

SAMPLE ANALYTE COUNT

PRECISION OIL & GAS, INC.

Project: 19230

Pace Project No.: 739155

Lab ID	Sample ID	Method	Analysts	Analytes Reported	Laboratory
739155001	19230	EPA 8015C	MRF	3	PASI-BVWV
		EPA 8015C	JWK	2	PASI-BVWV
		EPA 8260B	RAB1	8	PASI-BVWV

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

PROJECT NARRATIVE

PRECISION OIL & GAS, INC.

Project: 19230

Pace Project No.: 739155

Method: EPA 8015C

Description: 8015C GCS DRO Water

Client: STURM ENVIRONMENTAL SERVICES

Date: November 27, 2019

General Information:

1 sample was analyzed for EPA 8015C. All samples were received in acceptable condition with any exceptions noted below or on the chain-of custody and/or the sample condition upon receipt form (SCUR) attached at the end of this report.

Hold Time:

The samples were analyzed within the method required hold times with any exceptions noted below.

Sample Preparation:

The samples were prepared in accordance with EPA 3535A with any exceptions noted below.

Initial Calibrations (Including MS Tune as applicable):

All criteria were within method requirements with any exceptions noted below.

Continuing Calibration:

All criteria were within method requirements with any exceptions noted below.

Surrogates:

All surrogates were within QC limits with any exceptions noted below.

Method Blank:

All analytes were below the report limit in the method blank, where applicable, with any exceptions noted below.

Laboratory Control Spike:

All laboratory control spike compounds were within QC limits with any exceptions noted below.

Matrix Spikes:

All percent recoveries and relative percent differences (RPDs) were within acceptance criteria with any exceptions noted below.

Additional Comments:

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full
without the written consent of Pace Analytical Services, LLC

PROJECT NARRATIVE

PRECISION OIL & GAS, INC.

Project: 19230

Pace Project No.: 739155

Method: EPA 8015C

Description: 8015C GCV GRO Water

Client: STURM ENVIRONMENTAL SERVICES

Date: November 27, 2019

General Information:

1 sample was analyzed for EPA 8015C. All samples were received in acceptable condition with any exceptions noted below or on the chain-of custody and/or the sample condition upon receipt form (SCUR) attached at the end of this report.

Hold Time:

The samples were analyzed within the method required hold times with any exceptions noted below.

Initial Calibrations (including MS Tune as applicable):

All criteria were within method requirements with any exceptions noted below.

Continuing Calibration:

All criteria were within method requirements with any exceptions noted below.

Surrogates:

All surrogates were within QC limits with any exceptions noted below.

Method Blank:

All analytes were below the report limit in the method blank, where applicable, with any exceptions noted below.

Laboratory Control Spike:

All laboratory control spike compounds were within QC limits with any exceptions noted below.

Matrix Spikes:

All percent recoveries and relative percent differences (RPDs) were within acceptance criteria with any exceptions noted below.

Duplicate Sample:

All duplicate sample results were within method acceptance criteria with any exceptions noted below.

Additional Comments:

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC

PROJECT NARRATIVE

PRECISION OIL & GAS, INC.

Project: 19230

Pace Project No.: 739155

Method: EPA 8260B

Description: 8260 MSV UST

Client: STURM ENVIRONMENTAL SERVICES

Date: November 27, 2019

General Information:

1 sample was analyzed for EPA 8260B. All samples were received in acceptable condition with any exceptions noted below or on the chain-of custody and/or the sample condition upon receipt form (SCUR) attached at the end of this report.

Hold Time:

The samples were analyzed within the method required hold times with any exceptions noted below.

Initial Calibrations (including MS Tune as applicable):

All criteria were within method requirements with any exceptions noted below.

Continuing Calibration:

All criteria were within method requirements with any exceptions noted below.

Internal Standards:

All internal standards were within QC limits with any exceptions noted below.

Surrogates:

All surrogates were within QC limits with any exceptions noted below.

Method Blank:

All analytes were below the report limit in the method blank, where applicable, with any exceptions noted below.

Laboratory Control Spike:

All laboratory control spike compounds were within QC limits with any exceptions noted below.

Matrix Spikes:

All percent recoveries and relative percent differences (RPDs) were within acceptance criteria with any exceptions noted below.

QC Batch: 7690

A matrix spike and/or matrix spike duplicate (MS/MSD) were performed on the following sample(s): 739359010

M1: Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.

- MS (Lab ID: 43093)

- Toluene

Additional Comments:

This data package has been reviewed for quality and completeness and is approved for release.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS

PRECISION OIL & GAS, INC.

Project: 19230 INJECTION FLUID

Pace Project No.: 739155

Sample: 19230		Lab ID: 739155001		Collected: 11/19/19 08:00		Received: 11/22/19 17:30		Matrix: Water	
Parameters		Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qual
8015C GCS DRO Water		Analytical Method: EPA 8015C Preparation Method: EPA 3535A							
DRO (C10-C28)	1410	ug/L	202	1	11/25/19 10:18	11/25/19 19:21			
ORO (C20-C40)	595	ug/L	202	1	11/25/19 10:18	11/25/19 19:21			
Surrogates									
o-Terphenyl (S)	74	%.	14-126	1	11/25/19 10:18	11/25/19 19:21	84-15-1		
8015C GCV GRO Water		Analytical Method: EPA 8015C							
GRO (C06-C10)	12.0	mg/L	0.50	1		11/25/19 08:11			
Surrogates									
2,5-Dibromotoluene (S)	100	%.	49-147	1		11/25/19 08:11			
8260 MSV UST		Analytical Method: EPA 8260B							
Benzene	437	ug/L	10.0	10		11/27/19 05:24	71-43-2		
Toluene	291	ug/L	10.0	10		11/27/19 05:24	108-88-3		
Ethylbenzene	25.1	ug/L	1.0	1		11/26/19 10:22	100-41-4		
Xylene (Total)	400	ug/L	30.0	10		11/27/19 05:24	1330-20-7		
Surrogates									
Dibromofluoromethane (S)	94	%.	70-130	1		11/26/19 10:22	1868-53-7		
Toluene-d8 (S)	110	%.	70-130	1		11/26/19 10:22	2037-26-5		
4-Bromofluorobenzene (S)	104	%.	70-130	1		11/26/19 10:22	460-00-4		
1,2-Dichloroethane-d4 (S)	103	%.	70-130	1		11/26/19 10:22	17060-07-0		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC

PROJECT NARRATIVE

PRECISION OIL & GAS, INC.

Project: 19230

Pace Project No.: 739155

Method: EPA 8015C

Description: 8015C GCS DRO Water

Client: STURM ENVIRONMENTAL SERVICES

Date: November 27, 2019

General Information:

1 sample was analyzed for EPA 8015C. All samples were received in acceptable condition with any exceptions noted below or on the chain-of custody and/or the sample condition upon receipt form (SCUR) attached at the end of this report.

Hold Time:

The samples were analyzed within the method required hold times with any exceptions noted below.

Sample Preparation:

The samples were prepared in accordance with EPA 3535A with any exceptions noted below.

Initial Calibrations (including MS Tune as applicable):

All criteria were within method requirements with any exceptions noted below.

Continuing Calibration:

All criteria were within method requirements with any exceptions noted below.

Surrogates:

All surrogates were within QC limits with any exceptions noted below.

Method Blank:

All analytes were below the report limit in the method blank, where applicable, with any exceptions noted below.

Laboratory Control Spike:

All laboratory control spike compounds were within QC limits with any exceptions noted below.

Matrix Spikes:

All percent recoveries and relative percent differences (RPDs) were within acceptance criteria with any exceptions noted below.

Additional Comments:

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC

PROJECT NARRATIVE

PRECISION OIL & GAS, INC.

Project: 19230

Pace Project No.: 739155

Method: EPA 8015C

Description: 8015C GCV GRO Water

Client: STURM ENVIRONMENTAL SERVICES

Date: November 27, 2019

General Information:

1 sample was analyzed for EPA 8015C. All samples were received in acceptable condition with any exceptions noted below or on the chain-of custody and/or the sample condition upon receipt form (SCUR) attached at the end of this report.

Hold Time:

The samples were analyzed within the method required hold times with any exceptions noted below.

Initial Calibrations (Including MS Tune as applicable):

All criteria were within method requirements with any exceptions noted below.

Continuing Calibration:

All criteria were within method requirements with any exceptions noted below.

Surrogates:

All surrogates were within QC limits with any exceptions noted below.

Method Blank:

All analytes were below the report limit in the method blank, where applicable, with any exceptions noted below.

Laboratory Control Spike:

All laboratory control spike compounds were within QC limits with any exceptions noted below.

Matrix Spikes:

All percent recoveries and relative percent differences (RPDs) were within acceptance criteria with any exceptions noted below.

Duplicate Sample:

All duplicate sample results were within method acceptance criteria with any exceptions noted below.

Additional Comments:

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC

PROJECT NARRATIVE

PRECISION OIL & GAS, INC.

Project: 19230

Pace Project No.: 739155

Method: EPA 8260B

Description: 8260 MSV UST

Client: STURM ENVIRONMENTAL SERVICES

Date: November 27, 2019

General Information:

1 sample was analyzed for EPA 8260B. All samples were received in acceptable condition with any exceptions noted below or on the chain-of custody and/or the sample condition upon receipt form (SCUR) attached at the end of this report.

Hold Time:

The samples were analyzed within the method required hold times with any exceptions noted below.

Initial Calibrations (including MS Tune as applicable):

All criteria were within method requirements with any exceptions noted below.

Continuing Calibration:

All criteria were within method requirements with any exceptions noted below.

Internal Standards:

All internal standards were within QC limits with any exceptions noted below.

Surrogates:

All surrogates were within QC limits with any exceptions noted below.

Method Blank:

All analytes were below the report limit in the method blank, where applicable, with any exceptions noted below.

Laboratory Control Spike:

All laboratory control spike compounds were within QC limits with any exceptions noted below.

Matrix Spikes:

All percent recoveries and relative percent differences (RPDs) were within acceptance criteria with any exceptions noted below.

QC Batch: 7690

A matrix spike and/or matrix spike duplicate (MS/MSD) were performed on the following sample(s): 739359010

M1: Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.

- MS (Lab ID: 43093)

- Toluene

Additional Comments:

This data package has been reviewed for quality and completeness and is approved for release.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS

PRECISION OIL & GAS, INC.

Project: 19230 INJECTION FLUID

Pace Project No.: 739155

Sample: 19230		Lab ID: 739155001	Collected: 11/19/19 08:00		Received: 11/22/19 17:30		Matrix: Water	
Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qual
8015C GCS DRO Water		Analytical Method: EPA 8015C Preparation Method: EPA 3535A						
DRO (C10-C28)	1410	ug/L	202	1	11/25/19 10:18	11/25/19 19:21		
ORO (C20-C40)	595	ug/L	202	1	11/25/19 10:18	11/25/19 19:21		
<i>Surrogates</i>								
o-Terphenyl (S)	74	%.	14-126	1	11/25/19 10:18	11/25/19 19:21	84-15-1	
8015C GCV GRO Water		Analytical Method: EPA 8015C						
GRO (C06-C10)	12.0	mg/L	0.50	1		11/25/19 08:11		
<i>Surrogates</i>								
2,5-Dibromotoluene (S)	100	%.	49-147	1		11/25/19 08:11		
8260 MSV UST		Analytical Method: EPA 8260B						
Benzene	437	ug/L	10.0	10		11/27/19 05:24	71-43-2	
Toluene	291	ug/L	10.0	10		11/27/19 05:24	108-88-3	
Ethylbenzene	25.1	ug/L	1.0	1		11/26/19 10:22	100-41-4	
Xylene (Total)	400	ug/L	30.0	10		11/27/19 05:24	1330-20-7	
<i>Surrogates</i>								
Dibromofluoromethane (S)	94	%.	70-130	1		11/26/19 10:22	1868-53-7	
Toluene-d8 (S)	110	%.	70-130	1		11/26/19 10:22	2037-26-5	
4-Bromofluorobenzene (S)	104	%.	70-130	1		11/26/19 10:22	460-00-4	
1,2-Dichloroethane-d4 (S)	103	%.	70-130	1		11/26/19 10:22	17060-07-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC

QUALIFIERS

PRECISION OIL & GAS, INC.

Project: 19230

Pace Project No.: 739155

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.

ND - Not Detected at or above adjusted reporting limit.

TNTC - Too Numerous To Count

J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.

MDL - Adjusted Method Detection Limit.

PQL - Practical Quantitation Limit.

RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.

S - Surrogate

1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.

Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.

LCS(D) - Laboratory Control Sample (Duplicate)

MS(D) - Matrix Spike (Duplicate)

DUP - Sample Duplicate

RPD - Relative Percent Difference

NC - Not Calculable.

SG - Silica Gel - Clean-Up

U - Indicates the compound was analyzed for, but not detected.

N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.

Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.

TNI - The NELAC Institute.

LABORATORIES

PASI-BVW Pace Analytical Services - WestVirginia

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full
without the written consent of Pace Analytical Services, LLC

QUALITY CONTROL DATA CROSS REFERENCE TABLE

PRECISION OIL & GAS, INC.

Project: 19230

Pace Project No.: 739155

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
739155001	19230	EPA 3535A	7598	EPA 8015C	7687
739155001	19230	EPA 8015C	7670		
739155001	19230	EPA 8260B	7690		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

LIMS73 Lab Sample Condition Upon Receipt (West Virginia)



Client Name: _____

WO#: 739155

PH: DYC

Due Date: 12/11/19

CLIENT: STURMENYSER

Page 12 of 12

Courier: ☐ Fed Ex ☐ UPS ☐ USPS ☐ Client ☐ Commercial ☒ Pace ☐ Other: _____

Tracking #: _____

Custody Seal on Cooler/Box/Containers Present: ☐ yes ☒ noSeals intact: ☐ yes ☐ no

Thermometer Used

Type of Ice: Wet Blue None

Cooler Temperature

Observed Temp

1.8 °C

Correction Factor: +0.3 °C

Final Temp: 1.1 °C

Comments: _____

pH paper Lot#

Date and initials of person examining

contents: TW 11-22-19

	Yes	No	N/A	
Chain of Custody Present:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	1.
Chain of Custody Filled Out:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	2.
Chain of Custody Relinquished:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	3.
Sampler Name & Signature on COC:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	4.
Sample Labels match COC:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	5.
-Includes date/time/ID	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	6.
Matrix	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	7.
Samples Arrived within Hold Time:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	8.
Short Hold Time Analysis (<2hrs remaining):	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	9.
Rush Turn Around Time Requested:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	10.
Sufficient Volume:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	11.
Correct Containers Used:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	12.
-Face Containers Used:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	13.
Containers Intact:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	14.
Orthophosphate field filtered:	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	15.
Hex Or Aqueous sample field filtered:	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	16.
-pH adjusted within 24 hours? (If yes, indicate acid lot #)	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	17.
Filtered volume received for Dissolved tests:	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	18.
All containers have been checked for preservation:	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	19.
exceptions: VOA, coliform, O&G, LL Mercury, Non-aqueous matrix	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	20.
All containers meet method preservation requirements:	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Initial when completed: TW Date/time samples provided to lab: 11-22-19 1730
Headspace in VOA Vials:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Tests not preserved:
Trip Blank Present:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Initial when completed: TW Date: 11-22-19-
Trip Blank Custody Seals Present:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

Client Notification/ Resolution:

Person Contacted: _____

Date/Time: _____

Contacted By: _____

Comments/ Resolution: _____

☐ A check in this box indicates that additional information has been stored in ereports.

*PM review is documented electronically in LIMS, when the Project Manager closes the SRF Review schedule in LIMS. The status may be reviewed in the Status section of the Workorder Edit Screen.

December 16, 2019

Ms. Laurie Hiles
Sturm Environmental Services
P.O. Box 650
Bridgeport, WV 26330

RE: Project: 19005
Pace Project No.: 30337504
PRECISION OIL & GAS, INC.

Dear Ms. Hiles:

Enclosed are the analytical results for sample(s) received by the laboratory on November 22, 2019. The results relate only to the samples included in this report. Results reported herein conform to the most current, applicable TNI/NELAC standards and the laboratory's Quality Assurance Manual, where applicable, unless otherwise noted in the body of the report.

If you have any questions concerning this report, please feel free to contact me.

Sincerely,



Samantha Bayura
samantha.bayura@pacelabs.com
(724)850-5622
Project Manager

Enclosures



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

CERTIFICATIONS

PRECISION OIL & GAS, INC.

Project: 19005
Pace Project No.: 30337504

Pace Analytical Services Pennsylvania

1638 Roseytown Rd Suites 2,3&4, Greensburg, PA 15601
ANAB DOD-ELAP Rad Accreditation #: L2417

Alabama Certification #: 41590

Arizona Certification #: AZ0734

Arkansas Certification

California Certification #: 04222CA

Colorado Certification #: PA01547

Connecticut Certification #: PH-0694

Delaware Certification

EPA Region 4 DW Rad

Florida/TNI Certification #: E87683

Georgia Certification #: C040

Florida: Cert E871149 SEKS WET

Guam Certification

Hawaii Certification

Idaho Certification

Illinois Certification

Indiana Certification

Iowa Certification #: 391

Kansas/TNI Certification #: E-10358

Kentucky Certification #: KY90133

KY WW Permit #: KY0098221

KY WW Permit #: KY0000221

Louisiana DHH/TNI Certification #: LA180012

Louisiana DEQ/TNI Certification #: 4086

Maine Certification #: 2017020

Maryland Certification #: 308

Massachusetts Certification #: M-PA1457

Michigan/PADEP Certification #: 9991

Missouri Certification #: 235

Montana Certification #: Cert0082

Nebraska Certification #: NE-OS-29-14

Nevada Certification #: PA014572018-1

New Hampshire/TNI Certification #: 297617

New Jersey/TNI Certification #: PA051

New Mexico Certification #: PA01457

New York/TNI Certification #: 10888

North Carolina Certification #: 42706

North Dakota Certification #: R-190

Ohio EPA Rad Approval: #41249

Oregon/TNI Certification #: PA200002-010

Pennsylvania/TNI Certification #: 65-00282

Puerto Rico Certification #: PA01457

Rhode Island Certification #: 65-00282

South Dakota Certification

Tennessee Certification #: 02867

Texas/TNI Certification #: T104704188-17-3

Utah/TNI Certification #: PA014572017-9

USDA Soil Permit #: P330-17-00091

Vermont Dept. of Health: ID# VT-0282

Virgin Island/PADEP Certification

Virginia/VELAP Certification #: 9526

Washington Certification #: C868

West Virginia DEP Certification #: 143

West Virginia DHHR Certification #: 9964C

Wisconsin Approve List for Rad

Wyoming Certification #: 8TMS-L

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC



Pace Analytical Services, LLC
1638 Roseytown Road - Suites 2,3,4
Greensburg, PA 15601
(724)850-5600

SAMPLE SUMMARY

PRECISION OIL & GAS, INC.

Project: 19005

Pace Project No.: 30337504

Lab ID	Sample ID	Matrix	Date Collected	Date Received
30337504001	19005	Water	11/19/19 08:00	11/22/19 09:40

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



Pace Analytical Services, LLC
1638 Roseytown Road - Suites 2,3,4
Greensburg, PA 15601
(724)850-5600

SAMPLE ANALYTE COUNT

PRECISION OIL & GAS, INC.

Project: 19005

Pace Project No.: 30337504

Lab ID	Sample ID	Method	Analysts	Analytes Reported	Laboratory
30337504001	19005	EPA 900.0	ERT	2	PASI-PA
		EPA 903.1	MK1	1	PASI-PA
		EPA 904.0	VAL	1	PASI-PA

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

PROJECT NARRATIVE

PRECISION OIL & GAS, INC.

Project: 19005

Pace Project No.: 30337504

Method: EPA 900.0

Description: 900.0 Gross Alpha/Beta

Client: Sturm Environmental Services

Date: December 16, 2019

General Information:

1 sample was analyzed for EPA 900.0. All samples were received in acceptable condition with any exceptions noted below or on the chain-of custody and/or the sample condition upon receipt form (SCUR) attached at the end of this report.

Hold Time:

The samples were analyzed within the method required hold times with any exceptions noted below.

Method Blank:

All analytes were below the report limit in the method blank, where applicable, with any exceptions noted below.

Laboratory Control Spike:

All laboratory control spike compounds were within QC limits with any exceptions noted below.

Matrix Spikes:

All percent recoveries and relative percent differences (RPDs) were within acceptance criteria with any exceptions noted below.

Additional Comments:

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

PROJECT NARRATIVE

PRECISION OIL & GAS, INC.

Project: 19005

Pace Project No.: 30337504

Method: EPA 903.1

Description: 903.1 Radium 226

Client: Sturm Environmental Services

Date: December 16, 2019

General Information:

1 sample was analyzed for EPA 903.1. All samples were received in acceptable condition with any exceptions noted below or on the chain-of custody and/or the sample condition upon receipt form (SCUR) attached at the end of this report.

Hold Time:

The samples were analyzed within the method required hold times with any exceptions noted below.

Method Blank:

All analytes were below the report limit in the method blank, where applicable, with any exceptions noted below.

Laboratory Control Spike:

All laboratory control spike compounds were within QC limits with any exceptions noted below.

Matrix Spikes:

All percent recoveries and relative percent differences (RPDs) were within acceptance criteria with any exceptions noted below.

Additional Comments:

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full
without the written consent of Pace Analytical Services, LLC

PROJECT NARRATIVE

PRECISION OIL & GAS, INC.

Project: 19005
Pace Project No.: 30337504

Method: EPA 904.0
Description: 904.0 Radium 228
Client: Sturm Environmental Services
Date: December 16, 2019

General Information:

1 sample was analyzed for EPA 904.0. All samples were received in acceptable condition with any exceptions noted below or on the chain-of custody and/or the sample condition upon receipt form (SCUR) attached at the end of this report.

Hold Time:

The samples were analyzed within the method required hold times with any exceptions noted below.

Method Blank:

All analytes were below the report limit in the method blank, where applicable, with any exceptions noted below.

Laboratory Control Spike:

All laboratory control spike compounds were within QC limits with any exceptions noted below.

Matrix Spikes:

All percent recoveries and relative percent differences (RPDs) were within acceptance criteria with any exceptions noted below.

Additional Comments:

This data package has been reviewed for quality and completeness and is approved for release.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC

ANALYTICAL RESULTS - RADIOCHEMISTRY

PRECISION OIL & GAS, INC.

Project: 19005 INJECTION FLUID

Pace Project No.: 30337504

Sample: 19005 Lab ID: 30337504001 Collected: 11/19/19 08:00 Received: 11/22/19 09:40 Matrix: Water
PWS: Site ID: Sample Type:

Parameters	Method	Act ± Unc (MDC) Carr Trac	Units	Analyzed	CAS No.	Qual
Gross Alpha	EPA 900.0	1,012 ± 576 (839) C:NA T:NA	pCi/L	12/04/19 18:49	12587-46-1	
Gross Beta	EPA 900.0	980 ± 792 (1,435) C:NA T:NA	pCi/L	12/04/19 18:49	12587-47-2	
Radium-226	EPA 903.1	203 ± 60.0 (10.6) C:NA T:97%	pCi/L	12/13/19 14:36	13982-63-3	
Radium-228	EPA 904.0	438 ± 86.8 (28.3) C:95% T:82%	pCi/L	12/12/19 14:18	15262-20-1	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL - RADIOCHEMISTRY

PRECISION OIL & GAS, INC.

Project: 19005

Pace Project No.: 30337504

QC Batch: 373342

Analysis Method: EPA 900.0

QC Batch Method: EPA 900.0

Analysis Description: 900.0 Gross Alpha/Beta

Associated Lab Samples: 30337504001

METHOD BLANK: 1811764

Matrix: Water

Associated Lab Samples: 30337504001

Parameter	Act ± Unc (MDC) Carr Trac	Units	Analyzed	Qualifiers
Gross Alpha	0.166 ± 0.196 (0.360) C:NA T:NA	pCi/L	12/04/19 17:57	
Gross Beta	0.036 ± 0.349 (0.696) C:NA T:NA	pCi/L	12/04/19 17:57	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC

QUALITY CONTROL - RADIOCHEMISTRY

PRECISION OIL & GAS, INC.

Project: 19005
Pace Project No.: 30337504

QC Batch:	373629	Analysis Method:	EPA 903.1
QC Batch Method:	EPA 903.1	Analysis Description:	903.1 Radium-226
Associated Lab Samples:	30337504001		

METHOD BLANK:	1812947	Matrix:	Water
Associated Lab Samples:	30337504001		

Parameter	Act ± Unc (MDC) Carr Trac	Units	Analyzed	Qualifiers
Radium-226	-0.0215 ± 0.258 (0.534) C:NA T:92%	pCi/L	12/13/19 14:05	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL - RADIOCHEMISTRY

PRECISION OIL & GAS, INC.

Project: 19005

Pace Project No.: 30337504

QC Batch: 373628

Analysis Method: EPA 904.0

QC Batch Method: EPA 904.0

Analysis Description: 904.0 Radium 228

Associated Lab Samples: 30337504001

METHOD BLANK: 1812945

Matrix: Water

Associated Lab Samples: 30337504001

Parameter	Act ± Unc (MDC) Carr Trac	Units	Analyzed	Qualifiers
Radium-228	0.355 ± 0.347 (0.709) C:75% T:83%	pCi/L	12/12/19 11:15	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALIFIERS

PRECISION OIL & GAS, INC.

Project: 19005
Pace Project No.: 30337504

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.

ND - Not Detected at or above adjusted reporting limit.

TNTC - Too Numerous To Count

J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.

MDL - Adjusted Method Detection Limit.

PQL - Practical Quantitation Limit.

RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.

S - Surrogate

1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.

Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.

LCS(D) - Laboratory Control Sample (Duplicate)

MS(D) - Matrix Spike (Duplicate)

DUP - Sample Duplicate

RPD - Relative Percent Difference

NC - Not Calculable.

SG - Silica Gel - Clean-Up

U - Indicates the compound was analyzed for, but not detected.

N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.

Act - Activity

Unc - Uncertainty: For Safe Drinking Water Act (SDWA) analyses, the reported Unc. is the calculated Count Uncertainty (95% confidence interval) using a coverage factor of 1.96. For all other matrices (non-SDWA), the reported Unc. is the calculated Expanded Uncertainty (aka Combined Standard Uncertainty, CSU), reported at the 95% confidence interval using a coverage factor of 1.96.

Gamma Spec: The Unc. reported for all gamma-spectroscopy analyses (EPA 901.1), is the calculated Expanded Uncertainty (CSU) at the 95.4% confidence interval, using a coverage factor of 2.0.

(MDC) - Minimum Detectable Concentration

Trac - Tracer Recovery (%)

Carr - Carrier Recovery (%)

Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.

TNI - The NELAC Institute.

LABORATORIES

PASI-PA Pace Analytical Services - Greensburg

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

WO#: 30337504

Section A Required Client Information:		Section B Required Project Information:	
Company: St. John Environmental Address: PO Box 650 Bridgetown, WV 26330 Email To: Phone: Fax: Requested Due Date/TAT:	Report To: Copy To: Purchase Order No.: Project Name: Project Number:	Address: Pace Order Number: Pace Project Manager: Pace Profile #:	NPDES - UST - RCRA - DRINKING WATER - OTHER
Y AGENCY		Y AGENCY	
Page: 1756249		Page: 1756249	

Section D Required Client Information				Section E Required Project Information				Section F Requested Analysis Filtered (Y/N)				Section G Requested Analysis Filtered (Y/N)			
Matrix Codes MATRIX / CODE Drinking Water Waste Water Product Soil/Solid Oil Wipe Air Tissue Other				Matrix Codes MATRIX / CODE DW WW P SL CL WP AR TS OT				Matrix Codes MATRIX / CODE DW WW P SL CL WP AR TS OT				Matrix Codes MATRIX / CODE DW WW P SL CL WP AR TS OT			
SAMPLE ID (A-Z, 0-9 / -) Sample IDs MUST BE UNIQUE				SAMPLE TYPE (see valid codes to left)				SAMPLE TYPE (see valid codes to left)				SAMPLE TYPE (see valid codes to left)			
DATE				DATE				DATE				DATE			
TIME				TIME				TIME				TIME			
RELINQUISHED BY / AFFILIATION				RELINQUISHED BY / AFFILIATION				RELINQUISHED BY / AFFILIATION				RELINQUISHED BY / AFFILIATION			
DATE				DATE				DATE				DATE			
TIME				TIME				TIME				TIME			
ADDITIONAL COMMENTS				ADDITIONAL COMMENTS				ADDITIONAL COMMENTS				ADDITIONAL COMMENTS			
1	19005	016	11/19/19 0800	3	11/19/19 0800	3	11/19/19 0800	3	11/19/19 0800	3	11/19/19 0800	3	11/19/19 0800	3	11/19/19 0800
2															
3															
4															
5															
6															
7															
8															
9															
10															
11															
12															

Pittsburgh Lab Sample Condition Upon Receipt



Client Name: Sturm Environmental Project # 30337504

Courier: ☐ Fed Ex ☒ UPS ☐ USPS ☐ Client ☐ Commercial ☐ Pace Other _____

Tracking #: 1Z 281 271 03 7956 1956

Label <u>2</u>
LIMS Login <u>VT</u>

Custody Seal on Cooler/Box Present: ☐ yes ☒ no Seals Intact: ☐ yes ☒ no

Thermometer Used n/a Type of Ice: Wet Blue None

Cooler Temperature _____ Observed Temp _____ °C Correction Factor: _____ °C Final Temp: _____ °C

Temp should be above freezing to 6°C

Comments:	Yes	No	N/A	pH paper Lot#	Date and Initials of person examining contents:
Chain of Custody Present:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	1000391	SP 11/05/19
Chain of Custody Filled Out:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	1.	
Chain of Custody Relinquished:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	2.	
Sampler Name & Signature on COC:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	3.	
Sample Labels match COC:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	4. No signature	
-Includes date/time/ID Matrix: <u>WT</u>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	5. No date or time	
Samples Arrived within Hold Time:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	6.	
Short Hold Time Analysis (<72hr remaining):	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	7.	
Rush Turn Around Time Requested:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	8.	
Sufficient Volume:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	9.	
Correct Containers Used:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	10.	
-Pace Containers Used:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	11.	
Containers Intact:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	12.	
Orthophosphate field filtered	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	13.	
Hex Cr Aqueous sample field filtered	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	14.	
Organic Samples checked for dechlorination:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	15.	
Filtered volume received for Dissolved tests	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	16.	
All containers have been checked for preservation.	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	exceptions: VOA, coliform, TOC, O&G, Phenolics, Radon, Non-aqueous matrix	
All containers meet method preservation requirements.	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Initial when completed <u>SP</u>	Date/time of preservation
				Lot # of added preservative	
Headspace in VOA Vials (>6mm):	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	17.	
Trip Blank Present:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	18.	
Trip Blank Custody Seals Present	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Initial when completed: <u>SP</u>	Date: <u>11/05/19</u>
Rad Samples Screened < 0.5 mrem/hr	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		

Client Notification/ Resolution:

Person Contacted: _____ Date/Time: _____ Contacted By: _____

Comments/ Resolution:

☐ A check in this box indicates that additional information has been stored in e-report.

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DEHNR Certification Office (i.e. out of hold, incorrect preservative, out of temp, incorrect containers)

*PM review is documented electronically in LIMS. When the Project Manager closes the SRF Review schedule in LIMS. The review is in the Status section of the Workorder Edit Screen.

STURM ENVIRONMENTAL SERVICES

Main Office:
STURM ENVIRONMENTAL SERVICES
BRUSHY FORK ROAD
P.O. BOX 650
BRIDGEPORT, WV 26336
PHONE: 304-623-6549
FAX: 304-623-6552

STURM ENVIRONMENTAL SERVICES
610 D STREET
P.O. BOX 6337
SO. CHARLESTON, WV 25303
PHONE: 304-744-9864
FAX: 304-744-7866

REPORT TO: Client Name:

Address:

City/State/Zip:

Contact Person:

Telephone Number:

Email Address:

Sample Name: (Print)

Sampler Signature:

Project Name:

Special Reporting:

BILL TO: Client Name:

Address:

City/State/Zip:

Contact Person:

Telephone Number:

Email Address:

Purchase Order #:

TURN AROUND TIME:

Standard ☒ Rush (pre-packed envelopes may apply) Please Check One

1 DAY 2 DAY 3 DAY

COMPOSITE SAMPLE	GRAB SAMPLE	PRESERVATIVE	MATRIX	ANALYZE FOR:
<input checked="" type="checkbox"/>	<input type="checkbox"/>			

Sample ID / Description
Injection Fluid

START DATE
START TIME
END DATE
END TIME
DATE
TIME

Ice
OTHER
HCl
NaOH
H₂SO₄ Fuming
H₂SO₄ Glass
None
HNO₃
Groundwater
Wastewater
Drinking Water
Sludge
Soil
Other (specify):

of Bottles
Flow (gpm, cfs, mgd) circle one
Field pH
Field Conductivity
Field DO
Field Chlorine (mg/L or ug/L) circle one
Field Temp (F° or C°) circle one

Comments

Records retained for 5 years

Laboratory Comments:
Temperature Upon Receipt
Bottles Preserved?

N

Requested by:

Date
Time

Received by:

Date
Time

collected #

410 19

Section A

Required Client Information:

Company: **Station Environmental**

Address: **8140x 650**

Phone: **205-623-6349**

Requested Due Date: **11/19/2007**

Section B
Required Project Information:

Report To: **Mr. Bob Smith**

Copy To: **Station Environmental**

Purchase Order No.: **8455**

Project Name: **8455**

Project Number: **8455**

Section C
Invoice Information:

Attention: **Mr. Bob Smith**

Company Name: **Station Environmental**

Address: **8140x 650**

Phone: **205-623-6349**

Requested Due Date: **11/19/2007**

Page: **1**

of **1**

1756249

REGULATORY AGENCY

NPDES - GROUND WATER - DRINKING WATER

UST - RCRA - OTHER

Site Location

STATE: **AL**

Requested Analysis Filtered (Y/N)

Residual Chlorine (Y/N)

Page Project No/ Lab ID.

Temp In °C

Received on Ice (Y/N)

Custody Sealed Cooler (Y/N)

Samples Intact (Y/N)

Temp In °C

Received on Ice (Y/N)

Custody Sealed Cooler (Y/N)

Samples Intact (Y/N)

Temp In °C

Received on Ice (Y/N)

Custody Sealed Cooler (Y/N)

Samples Intact (Y/N)

Temp In °C

Received on Ice (Y/N)

Custody Sealed Cooler (Y/N)

Samples Intact (Y/N)

Temp In °C

Received on Ice (Y/N)

Custody Sealed Cooler (Y/N)

Samples Intact (Y/N)

Temp In °C

Received on Ice (Y/N)

Custody Sealed Cooler (Y/N)

Samples Intact (Y/N)

Temp In °C

Received on Ice (Y/N)

Custody Sealed Cooler (Y/N)

Samples Intact (Y/N)

Temp In °C

Received on Ice (Y/N)

Custody Sealed Cooler (Y/N)

Samples Intact (Y/N)

Temp In °C

Received on Ice (Y/N)

Custody Sealed Cooler (Y/N)

Samples Intact (Y/N)

Temp In °C

Received on Ice (Y/N)

Custody Sealed Cooler (Y/N)

Samples Intact (Y/N)

Temp In °C

Received on Ice (Y/N)

Custody Sealed Cooler (Y/N)

Samples Intact (Y/N)

Temp In °C

Received on Ice (Y/N)

Custody Sealed Cooler (Y/N)

Samples Intact (Y/N)

Important Note: By signing this form you are accepting Pact's NET 30 day payment terms and agreeing to pay charges of \$1.50 per month for any invoices not paid within 30 days.

F-ALL-Q-020rev 07, 15-May-2007



GEOCHEMICAL TESTING

Environmental and Energy Analysis

2005 N. Center Ave.
Somerset, PA 15501

814/443-1671
814/445-6666
FAX: 814/445-6729

Wednesday, November 27, 2019

VICKI HOOPS
STURM ENVIRONMENTAL SERVICES
PO BOX 650
BRIDGEPORT, WV 26330
PRECISION OIL & GAS, INC.

Order No.: G1911C92

Dear VICKI HOOPS:

Geochemical Testing received 1 sample(s) on 11/22/2019 for the analyses presented in the following report.

There were no problems with sample receipt protocols and analyses met the TNI/NELAC, EPA, and laboratory specifications except where noted in the Case Narrative or Laboratory Results.

If you have any questions regarding these tests results, please feel free to call.

Sincerely,

Timothy W. Bergstresser
Director of Technical Services



Geochemical Testing

Date: 27-Nov-19

CLIENT: STURM ENVIRONMENTAL SERVICES
Project: PRECISION OIL & GAS, INC.
Lab Order: G1911C92 PWS: 9999999

CASE NARRATIVE

No problems were encountered during analysis of this workorder, except if noted in this report.

Legend:

H - Method Hold Time exceeded and is not compliant with 40CFR136 Table II.

U - The analyte was not detected at or above the listed concentration, which is below the laboratory quantitation limit.

B - Analyte detected in the associated Method Blank

QI - See case narrative ND - Not Detected

MCL - Contaminant Limit J - Indicates an estimated value.

Q - Qualifier QL - Quantitation Limit DF - Dilution Factor

S - Surrogate Recovery outside accepted recovery limits

T - Sample received above required temperature and is not compliant with 40CFR136 Table II.

TI - Sample received above required temperature

MDA - Minimum Detectable Activity.

** - Value exceeds Action Limit

TICs - Tentatively Identified Compounds

E - Value above quantitation range



I.D. 56-00306 PA DEP

Laboratory Results

Geochemical Testing

Date: 27-Nov-19

CLIENT:	STURM ENVIRONMENTAL SERVICES	Client Sample ID: 19022
Lab Order:	G1911C92	
Project:	PRECISION OIL & GAS, INC.	Collection Date: 11/19/2019 8:00:00 AM
Lab ID:	G1911C92-001 INJECTION FLUID	Sampled By: Sturm Environmental
Matrix:	AQUEOUS	Date Received: 11/22/2019 10:33:22 AM

Analyses	Result	Q	MDL	PQL	Units	DF	Date Prepared	Date Analyzed
DISSOLVED GASSES			Analyst: TEW			ASTM D8028		ASTM D8028
Butane, dissolved	0.52		0.010	0.020	mg/L	1	11/25/19 4:04 PM	11/25/19 6:58 PM
Ethane, dissolved	1.4		0.010	0.020	mg/L	1	11/25/19 4:04 PM	11/25/19 6:58 PM
Methane, dissolved	0.76		0.010	0.020	mg/L	1	11/25/19 4:04 PM	11/25/19 6:58 PM
Propane, dissolved	1.3		0.010	0.020	mg/L	1	11/25/19 4:04 PM	11/25/19 6:58 PM
Surr: Ethoxyethane	132	S	0	70-130	%REC	1	11/25/19 4:04 PM	11/25/19 6:58 PM

Shuttle/Cooler ID#: 020

CHAIN OF CUSTODY

Geochemical Testing

Geochemical Testing • 2005 North Center Avenue • Somerset PA 15501 • (814) 443-1671 • Fax (814) 445-6729

Form F-5002, 11/16

Billing Client: Sturm Environmental

Address: PO Box 650

City: B. Report State: WV Zip: 26330

WO#: G194692

Contact (Company): Sturm
E-Mail: mhobbs@sturmenvironmental.com
Sampled by: B. Jones
Project:

Phone: (304) 623-6549

Fax: ()

State Sampled: WV

POL/Case#: 8454

Sample Matrix:	GW Ground Water	SW Surface Water	PW Potable Water	WW Wastewater	SO Soil	SL Sludge	Hz Not Hazardous / Hz Hazardous	PCBs
Sample Type:	G Grab	C Composite	D Distribution/DW	R Raw/DW	S Spec/DW	O Other		

Sample Location/

Description

Lab

Number

Sample

Date

Time

Type

Analyses Requested

Remarks/

Preservatives, etc

*NOTE: If multiple analytes from one bottle, OR if multiple bottles for one analyte, THEN list separately on one line UNLESS LISTED ON ATTACHED FIELD LOG

19022

001

L

11-19-19

0800

G

Dissolved Gases: Ethane

Field Filtered: Y/N

3

Methane

Field Filtered: Y/N

Propane

Field Filtered: Y/N

Butane

Field Filtered: Y/N

Field Filtered: Y/N

Field Filtered: Y/N

Note Deficiencies Here:

Relinquished by (Company & Signature)

Date

Time (Military)

Received by (Company & Signature)

Date

Time (Military)

C. Michael / Sturm Environmental

11-21-19

PM

Shirley Kelle

11-22-19

10:33

SAMPLES MUST BE PRESERVED ON ICE.

Ice present on receipt:

Yes or No

Cooler Temp (°C) on receipt:

Sample Receiving (1st Review):

Client Support (2nd Review):

**STURM ENVIRONMENTAL SERVICES
610 D STREET
P.O. BOX B337
SO. CHARLESTON, WV 25303
PHONE: 304-744-9864
FAX: 304-744-7866**

Precision Oil & Gas
P.O. Box 884

Address:

Bridgeport, NY 26330

City/State/Zip:

Black Boxes

Contact Person:

304-709-8382 Fax No.

Telephone Number:

FBI No.

510743 422@gmail.com

Email Address:

Elyse Jones

Purchase Order

Step 62

THEIR AGENDA TIME:

Tarif ulc

Standard

7/25/17 - WIC

RUSH (pre-scheduled; surcharges may apply) Please Check One

1 DAY 2 DAY 3 DAY

Special Reportings:		<input checked="" type="checkbox"/> Final Results	<input type="checkbox"/> For Results	Date Needed
Sample ID / Description <i>Injection Fluid</i>	COMPOSITE SAMPLE	START DATE	GROSS SAMPLE	ANALYZE FOR:
	START TIME	END DATE	DATE	
	END TIME	TIME	PRESERVATIVE	
		Ice	MATRIX	
		OTHER		
		HCl HNO ₃ H ₂ SO ₄ , Plantar. H ₂ O ₂ , Urea Rose HNO ₃ Groundwater Ventilation Drinking Water Sludge Soil Other (specify): <i>Big Set</i>		
	# of Bottles	Flow (gpm, cfs, mgd) circle one		
	Field pH			
	Field Conductivity			
	Field DO			
	Field Chlorine (mg/L or ug/L) circle one			
	Field Temp (F° or C°) circle one			

Records retained for 5 years

Laboratory Components:

**Temperature Upon Receipt:
Bottles Preserved?**

五

Date	Time
11/19/17	10:30

Received by:

13

Date	Time
11-18-15	16:30

collier &

五

COMPANY: PRECISION OIL & GAS, INC.

DATE/TIME SAMPLED: 11-19-19 0800

SAMPLE ID: INJECTION FLUID

DATE/TIME RECEIVED: 11-19-19 1030

SAMPLED BY: B. JONES

LABORATORY ID: POG 191119-1

PARAMETER	TEST RESULTS	UNITS	METHOD	METHOD DETECTION LIMIT	DATE/TIME ANALYZED	ANALYST
pH	5.1	units	SM 22 nd 4500 H B	.1	11-20-19 1731	HN
Fe	194.	mg/L	EPA 200.7 Rev 4.4-1994	.05	11-21-19 0726	DB
Mn	3.99	mg/L	EPA 200.7 Rev 4.4-1994	.002	11-21-19 0726	DB
TSS	140	mg/L	USGS I-3765-85	4	11-21-19 1401	MRM/EK
TDS	105160	mg/L	USGS I-1750-85	4	11-21-19 1401	MRM/EK
MBAS	.78	mg/L	SM22 nd 5540C	.02	11-20-19 2313	SW
TOC	276.	mg/L	SM22 nd 5310B	2.0	12-02-19 1647	LM
SO ₄	385.	mg/L	EPA 300.0 Rev 2.1-1993	1.0	11-21-19 0332	DC
Cl ⁻	57400.	mg/L	EPA 300.0 Rev 2.1-1993	1.0	11-21-19 0322	DC
Al	.56	mg/L	EPA 200.7 Rev 4.4-1994	.04	11-21-19 0726	DB
As	.63	mg/L	EPA 200.7 Rev 4.4-1994	.04	11-26-19 0529	DB
Ba	42.2	mg/L	EPA 200.7 Rev 4.4-1994	.003	11-21-19 0726	DB
Ca	9273.	mg/L	EPA 200.7 Rev 4.4-1994	.15	11-21-19 0726	DB
Na	25600.	mg/L	EPA 200.7 Rev 4.4-1994	.05	11-21-19 0726	DB
SPEC GRAVITY	1.07051	calc	CALCULATION		11-20-19 1743	SW

*Client Provided

**See Attached The following results meet or exceed requirements and standards set forth by the certifying authority except where noted.

Data Qualifiers

- B Analyte found in reagent blank. Indicates possible reagent or background contamination
- E Estimated Reported value exceeded calibration range.
- J Reported value is an estimate because concentration is less than reporting limit.
- PND Precision not determined.
- R Sample results rejected because of gross deficiencies in QC or method performance. Re-sampling and/or re-analysis is necessary.
- RND Recovery not determined.
- U Compound was analyzed for, but not detected.
- O Out of holding. Time does not meet 40 CFR 136/141 compliance.
- T This result is not supported by our certification ID.
- A Does not meet 40 CFR 136/141 compliance.
- C Does not meet 47 CSR 32 compliance.

Narrative:

Approved

Doyle H. Burt

VICTORIA L. HODDS, PRESIDENT

COMPANY: PRECISION OIL & GAS, INC.

DATE/TIME SAMPLED:* 11-19-19 0800

SAMPLE ID: INJECTION FLUID

DATE/TIME RECEIVED: 11-19-19 1030

SAMPLED BY: B. JONES

LABORATORY ID: POG 191119-1

LOG NO: W554-19

[illegible]

*Client Provided

****See Attached. The following results meet or exceed requirements and standards set forth by the certifying authority except where noted.**
Microbiological analysis results will be discarded after 5 years

Method of Analysis from "Standard Methods for the Examination of Water and Wastewater,"

Data Qualifiers

B Analyte found in reagent blank. Indicates possible reagent or background contamination.

E Estimated Reported value exceeded calibration range.

J Reported value is an estimate because concentration is less than reporting limit.

PND Precision not determined.

R Sample results rejected because of gross deficiencies in QC or method performance. Re-sampling and/or re-analysis is necessary.

RND Recovery not determined.

U Compound was analyzed for, but not detected.

Out of holding. Time does not meet 40 CFR 136/141 compliance.

T This result is not supported by our certification ID.

A Does not meet 40 CFR 136/141 compliance.

C Does not meet 47 CSR 32 compliance.

Narrative:

Approved

Douglas H Buntz

Section 10

Monitoring

Section 10

Monitoring

The monitoring plan for the Tariff Field will be in compliance with all permit conditions and applicable UIC rules and regulations and will consist of the following:

1. Daily visual inspection and integrity check of pump equipment, storage tanks, secondary containment structures, storage tank valves, distribution lines, headers, and well heads.
2. Daily monitoring and recording of the maximum injection pressure, injection volumes, and hours of operation.
3. Daily monitoring and recording of annulus pressures either by gauge or chart recorder.
4. Monthly submission of all required injection data to the ESS website as compiled on the WR-40 form.
5. Submission of all corrective action data as required by the permit.
6. Monthly inspections of spill response equipment on site.

Section 11

Groundwater Protection Plan

APPENDIX H

GROUNDWATER PROTECTION PLAN

Facility Name: Tariff Field - See Attached SPCCCounty: RoaneFacility Location: Tariff

Postal Service Address:	1422 Tariff Road		
	Left hand WV 25251		
Latitude :	38.662600	Longitude:	81.2123999

Contact Information:

Person:	Jodi Sutro
Phone Number:	(304) 587-4477
E-mail Address:	jodi.sutro@groundresourcesllc.com

Date: 10/26/17

1. A list of all operations that may contaminate the groundwater.

Oil / Gas Production, Water injection.

possible injection and gathering pipeline leaks,
possible containment structure leaks,
possible equipment leaks,
possible tank truck leaks if used.

2. A description of procedures and facilities used to protect groundwater quality from the list of potential contaminant sources above.

Secondary Containment has been installed to contain 110% of liquids stored. Spill response equipment is stored at Office Field Office.

3. List procedures to be used when designing and adding new equipment or operations.

Secondary Containment will be installed for new equipment.

RECEIVED
Office of Oil and Gas

OCT 31 2017

WV Department of
Environmental Protection

dep

4. Summarize all activities at your facility that are already regulated for groundwater protection.

Oil/gas production, water injection

5. Discuss any existing groundwater quality data for your facility or an adjacent property.

Water samples have been analyzed to establish a baseline for previous permits

6. Provide a statement that no waste material will be used for deicing or fill material on the property unless allowed by another rule.

No Waste Water will be used for deicing or fill material on the property unless allowed by another Rule

7. Describe the groundwater protection instruction and training to be provided to the employees. Job procedures shall provide direction on how to prevent groundwater contamination.

Employees have received training on how to best management practices and spill response during safety training sessions.

RECEIVED
Office of Oil and Gas
OCT 31 2017
WV Department of
Environmental Protection

dep

8. Include provisions for inspections of all GPP elements and equipment. Inspections must be made quarterly at a minimum.

Provisions for inspections have been included in the SPCC Plan.

Signature:

David L. Huh

Date:

10/30/17

RECEIVED
Office of Oil and Gas
OCT 31 2017
WV Department of
Environmental Protection

dep

Section 12

Plugging & Abandonment

Section 12

A well work plugging permit must be obtained from the West Virginia Department of Environmental Protection Office of Oil and Gas before beginning any well plugging operation. Plan will be in compliance with all applicable plugging and abandonment regulations including 35CSR4-13. The guidelines provided in Oil and Gas rule and code will be followed to complete the necessary application to plug and abandon. The cement plug will be a minimum of 100 feet in thickness. A cement plug will be set above any perforation(s) and/or shot hole(s). All casings will be free pointed and as much casing will be removed as possible. A cement plug will be used to separate oil and gas bearing formations. A cement plug will be placed across all casing cuts. An elevation plug will be placed in each. If surface casing is cemented to surface a cement plug will be placed across the shoe and at the surface. If there is no cemented surface casing then a cement plug will be placed across fresh water zone and at the surface. Gel will be used as a spacer between all cement plugs.

Section 13

Additional Bonding

Section 13

Not applicable.

RECEIVED
Office of Oil and Gas

OCT 31 2017

WV Department of
Environmental Protection

Section 14

Financial Responsibility

APPENDIX I

Requirement for Financial Responsibility to Plug/Abandon an Injection Well

To: WV Department of Environmental Protection
Office of Oil and Gas
601 57th Street, SE
Charleston, West Virginia 25304-2345
ATTN: Underground Injection Control Program

From: Ground Resources, LLC
513 Charleston Road
Spencer, WV 25276

Date:

10/26/17

Subject: Underground Injection Control (UIC) Permit Application
#2R08702AF
Requirement for Financial Responsibility

I, David W Heeter, verify in accordance with 47CSR13-13.7.g., that I will maintain financial responsibility and resources to close, plug, and abandon underground injection wells(s) in a manner prescribed by the Chief of the Office of Oil and Gas.

Name:

David W. Heeter

Signature:

David Heeter

Date:

10/26/17

RECEIVED
Office of Oil and Gas
OCT 31 2017
WV Department of
Environmental Protection

Section 15

Site Security Plan

Section 15

Not applicable

RECEIVED
Office of Oil and Gas
OCT 31 2017
WV Department of
Environmental Protection

Section 16

Additional Information

Section 16

See Appendix K

RECEIVED
Office of Oil and Gas

OCT 31 2017

WV Department of
Environmental Protection



APPENDIX K

**Identify permit or construction approvals received
or applied for under the following programs:**

Permit/approvals	ID Number
Hazardous Waste Management Program under RCRA	
NPDES Program	
Prevention of Significant Deterioration (PSD)	
Nonattainment Program	
Dredge or Fill	
NPDES/NPDES – Stormwater	
WVDEP – Office of Waste Management (OWM) – Solid Waste Facility	
WVDEP – OWM – RCRA (Hazardous Waste TSD or Transporter)	
WVDEP – OWM – UST	
CERCLA – Superfund	
WV Voluntary Remediation – Brownfields	
FIFRA – Federal Insecticide, Fungicide and Rodenticide Act	
Well Head Protection Program (WHPP)	
Underground Injection Control (UIC)	2R08702AP
Toxic Substances Control Act (TSCA)	
Best Management Plans	STATE GUIDELINES
Management of Used Oil	
Other Relevant Permits (Specify):	

TARIFF FIELD

Ground Resources, LLC
Tariff Field
UIC Permit 2R08700008AP
Revised 7/20/2020



LEGEND

AOR BUFFER

- TARIFF FIELD BOUNDARY
- 1 MILE AOR
- 25 MILE AOR

INJECTOR - SHUT IN

- INJECTOR - SHUT IN

INJECTOR - PLUGGED

- INJECTOR - PLUGGED

2R OIL PRODUCTION


- Active Well
- Abandoned Well
- Plugged

OIL PRODUCTION

- Active Well
- Abandoned Well
- Plugged
- Pre-1929 Unknown

GAS PRODUCTION

- Active Well
- Abandoned Well
- Plugged




1 inch = 500 feet

PREPARED BY:
BLAKE JONES, GIS SPECIALIST
PRECISION OIL AND GAS, INC.

TARIFF FIELD

Ground Resources, LLC
Tariff Field
UIC Permit 2R08700008AP
Revised 7/20/2020



LEGEND

AOR BUFFER

TARIFF FIELD BOUNDARY

1 MILE AOR

25 MILE AOR

INJECTOR - SHUT IN

INJECTOR - SHUT IN

INJECTOR - PLUGGED

INJECTOR - PLUGGED

2R OIL PRODUCTION

Active Well

Abandoned Well

Plugged

Pre-1929 Unknown

OIL PRODUCTION

Active Well

Abandoned Well

Plugged


Pre-1929 Unknown

GAS PRODUCTION

Active Well

Abandoned Well

Plugged



1 inch = 900 feet